

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-151-21425-00-00
Spot: S2S2SE Sec/Twnshp/Rge: 25-28S-11W
330 feet from S Section Line, 1320 feet from E Section Line
Lease Name: SWICK Well #: 1
County: PRATT Total Vertical Depth: 2870 feet

Operator License No.: 3842
Op Name: LARSON ENGINEERING, INC. DBA LAR
Address: 562 W STATE RD 4
OLMITZ, KS 67564

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2870	1640	WITH 200 SX CMT
SURF	8.625	411		325 SX

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 08/13/2015 11:30 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: RICHARD MCINTYRE Company: QUALITY WELL SERVICE, INC. Phone: (620) 727-3410

Proposed Plugging Method: PUMP 25 SX CMT WITH 150# HULLS PLUG AT 720' WITH 10 SX GEL & 50 SX CMT. PLUG AT 440' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN Witness Type: NONE
Date/Time Plugging Completed: 08/13/2015 2:30 PM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

PUMPED 25 SX CMT WITH 150# HULLS. PRESSURED TO 1600#. TOC 2500'. 1ST PLUG AT 740' WITH 10 SX GEL & 50 SX CMT. 2ND PLUG AT 440' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 30 SX CMT.

Perfs:

Top	Bot	Thru	Comments
2614	2634		

Remarks: USED 60/40 POZMIX 4% GEL BY QUALITY WELL SERVICE.

Plugged through: CSG

SEP 02 2015
CKM

District: 01

Signed Eric MacLaren
(TECHNICIAN)

SA

KCC WICHITA

RECEIVED
AUG 21 2015
KCC DODGE CITY

AUG 26 2015
RECEIVED