

TO:

STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-207-20061-00-02

Spot: SWSWSWSW

Sec/Twnshp/Rge: 16-25S-16E

250 feet from S Section Line, 5030 feet from E Section Line

Lease Name: COFFIELD

Well #: 3

County: WOODSON

Total Vertical Depth: 1050 feet

Operator License No.: 32710

Op Name: LAYMON OIL II, LLC

Address: 1998 SQUIRREL RD.

NEOSHO FALLS, KS 66758

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2.875	1040		0 SX
SURF	7	40		0 SX

Well Type: OIL

UIC Docket No:

Date/Time to Plug: 06/24/2015 12:00 AM

Plug Co. License No.: 32710

Plug Co. Name: LAYMON OIL II, LLC

Proposal Rcvd. from: LAYMON OIL II LLC

Company:

Phone: (620) 963-2495

Proposed Run 1" pipe into 2.875" casing to the bottom. Pump cement into 1" until cement circulates to surface. Remove 1" and
Plugging pump cement into 2.875" casing to the surface.
Method:

Plugging Proposal Received By:

WitnessType: NONE

Date/Time Plugging Completed: 06/24/2015 8:00 AM

KCC Agent: RYAN DULING

Actual Plugging Report:

Perfs:

Hooked onto the 2.875" casing at surface. Broke circulation. Pumped 30 sacks of portland cement into the 2.875" casing. Pressured well up and shut well in with 600 psi. A total of 30 sacks of portland cement was reported used to plug this well.

RECEIVED
KCC DIST #3
AUG 25 2015
CHANUTE, KS

RD

Remarks:

Plugged through: CSG

District: 03

Signed

[Signature]
(TECHNICIAN)

SEP 02 2015
CKM

KCC WICHITA

AUG 28 2015

RECEIVED