

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-207-20066-00-00  
Spot: SESESE Sec/Twnshp/Rge: 17-25S-16E  
330 feet from S Section Line, 330 feet from E Section Line  
Lease Name: KENNETH STOCKEBRAND Well #: 1  
County: WOODSON Total Vertical Depth: 1050 feet

Operator License No.: 32710  
Op Name: LAYMON OIL II, LLC  
Address: 1998 SQUIRREL RD  
NEOSHO FALLS, KS 66758

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	953		0 SX
SURF	7	40		0 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 06/24/2015 12:00 AM  
Plug Co. License No.: 32710 Plug Co. Name: LAYMON OIL II, LLC  
Proposal Rcvd. from: LAYMON OIL II, LLC Company: \_\_\_\_\_ Phone: (620) 963-2495

Proposed Plugging Method: Run 2" tubing into 4.5" casing to bottom. Pump cement into 2" until cement circulates to surface. Remove 2" tubing and pump cement into 4.5" casing to surface.

Plugging Proposal Received By: \_\_\_\_\_ Witness Type: NONE  
Date/Time Plugging Completed: 06/24/2015 8:00 AM KCC Agent: RYAN DULING

Actual Plugging Report:

Hooked onto 4.5" casing at surface. Broke circulation. Mixed and pumped cement and cottonseed hulls through the 4.5" casing from surface to TD. Pressured up and shut in at 800 psi. A total of 50 sacks of cement and 10 sacks of cottonseed hull were reported used to plug this well.

Perfs:

RECEIVED  
KCC DIST # 3  
AUG 25 2015  
CHANUTE, KS

R.D

Remarks:

Plugged through: CSG

SEP 02 2015  
CKM

District: 03

Signed \_\_\_\_\_

(TECHNICIAN)

KCC WICHITA

AUG 28 2015

RECEIVED