

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-207-24724-00-01
Spot: SWSWNENW Sec/Twnshp/Rge: 2-24S-15E
4280 feet from S Section Line, 3785 feet from E Section Line
Lease Name: SMITH A Well #: 1
County: WOODSON Total Vertical Depth: 1539 feet

Operator License No.: 33900

Op Name: LEIS, STEVEN A.

Address: 1135 30TH RD
YATES CENTER, KS 66783

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	2.875	1539		250 SX
SURF	7	40		8 SX

Well Type: EOR UIC Docket No: E23199.1 Date/Time to Plug: 08/11/2015 12:00 AM

Plug Co. License No.: 33900 Plug Co. Name: LEIS, STEVEN A.

Proposal Rcvd. from: STEVE LEIS Company: Phone: (620) 330-6328

Proposed Plugging Method: Will run a string of 1" tubing in well and plug the bottom off then, then plug the BKC. And also plug from 250 ft up to surface. After the well is plugged we will then cut the old casing off below ground level.

Plugging Proposal Received By: WitnessType: NONE
Date/Time Plugging Completed: 08/11/2015 8:00 AM KCC Agent: RYAN DULING

Actual Plugging Report:

Ran 1" pipe down the 2.875" casing to TD. Mixed and pumped gel at TD. Pumped and place a 100' plug at TD. Pulled 1" pipe up to 785' to the base of the Kansas City. Placed a 100' cement plug at 785'. Pulled 1" pipe up to 250'. Pumped and circulated cement from 250' to surface. Pulled the rest of the 1" pipe out of the hole and topped the well off with cement. A total of 18 sacks of portland cement was reported used to plug this well.

Perfs:

Top	Bot	Thru	Comments
1506	1510		
RECEIVED KCC DIST # 3 AUG 25 2015 CHANUTE, KS RD			

Remarks:

Plugged through: TBG

SEP 02 2015
CKM

District: 03

Signed [Signature]
(TECHNICIAN)

KCC WICHITA

AUG 28 2015

RECEIVED

UIC