

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-055-00512-00-00  
Spot: SE Sec/Twnshp/Rge: 20-25S-31W  
2540 feet from S Section Line, 2540 feet from E Section Line  
Lease Name: BEACH Well #: 3  
County: FINNEY Total Vertical Depth: 2635 feet

Operator License No.: 33999  
Op Name: LINN OPERATING, INC.  
Address: 600 TRAVIS STE 4900  
HOUSTON, TX 77002

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		1050		
PROD	5.5	2592	0	WITH 150 SX CMT
SURF	8.625	536		WITH 300 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/20/2015 8:00 AM  
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.  
Proposal Rcvd. from: REUBEN Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 08/20/2015 5:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

TAGGED FILL UP FROM CASING LEAK AT 1600'. PUMP 50 SX CMT AT 1580'. CIRCULATED. CIBP @ 1050' OVER CASING LEAK. TEST CASING AT 800#. HOLDING. PERFORATE AT 1000'. RUN TBG & PACKER TO 570'. INJECTION RATE 1 1/2 BPM @ 400# THROUGH PERFS AT 1000'. PUMP 40 SX CMT, 50# HULLS THEN 40 SX CMT. DISPLACE TO 600'. TOOH WITH TBG & PACKER. TAG TOC WITH ELECTRIC LINE AT 630'. PERFORATE AT 570'. INJECTION RATE 2 1/2 BPM AT 150#. CIRCULATE CMT THROUGH PERFS TO SURFACE WITH 200 SX CMT LEAVING THE 5 1/2" CASING & 5 1/2" ANNULUS FULL OF CMT.

Perfs:

Top	Bot	Thru	Comments
2593	2618	OH	

Remarks: USED CLASS C COMMON CEMENT BY ORR ENTERPRISES.

Plugged through: TBG

SEP 02 2015  
CKM

District: 01

Signed *Ken Jehlik*  
JA (TECHNICIAN)

RECEIVED  
AUG 24 2015  
KCC DODGE CITY

KCC WICHITA  
Form CP-2/3

AUG 26 2015

RECEIVED