

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-189-20040-00-00  
Spot: SW Sec/Twnshp/Rge: 30-31S-37W  
1258 feet from S Section Line, 3847 feet from E Section Line  
Lease Name: MUSGROVE Well #: 2-30  
County: STEVENS Total Vertical Depth: 2955 feet

Operator License No.: 33999  
Op Name: LINN OPERATING, INC.  
Address: 600 TRAVIS STE 4900  
HOUSTON, TX 77002

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		1100		WITH 10 SX CMT
CIBP		2776		WITH 2 SX CMT
PROD	5.5	2954	0	WITH 300 SX CMT
SURF	8.625	570		WITH 500 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/17/2015 9:00 AM  
Plug Co. License No.: 33338 Plug Co. Name: ORR ENTERPRISES, INC.  
Proposal Rcvd. from: RONNIE ORR Company: ORR ENTERPRISES, INC. Phone: (580) 251-9618

Proposed Plugging Method: CIBP @ 2776' WITH 2-SX CMT. PLUG AT 1750' WITH 100 SX CMT. CIBP @ 1100' WITH 2 SX CMT. PERFORATE 4 HOLES AT 600' & CIRCULATE CMT TO SURFACE.

Plugging Proposal Received By: KEN JEHLIK Witness Type: PARTIAL  
Date/Time Plugging Completed: 08/17/2015 5:00 PM KCC Agent: WADE KLAUS

Actual Plugging Report:

CIBP @ 2776' WITH 2 SX CMT. PLUG AT 1750' WITH 100 SX CMT. CIBP @ 1100' WITH 10 SX CMT. FILL HOLE & PRESSURE TEST TO 750 PSI. PERFORATE AT 600'. PUMPED 204 SX CMT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
2826	2948		

KCC WICHITA

AUG 26 2015

RECEIVED  
SEP 02 2015  
CKM

Remarks: USED COMMON CEMENT BY ORR ENTERPRISES

Plugged through: TBG

District: 01

Signed [Signature]

(TECHNICIAN)

RECEIVED  
AUG 19 2015  
KCC DODGE CITY [Signature]