

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-051-25154-00-00
Spot: NWSWNWNW Sec/Twnshp/Rge: 5-11S-20W
4793 feet from S Section Line, 5273 feet from E Section Line
Lease Name: RICHARDS-FISCHER UNIT Well #: 1-5
County: ELLIS Total Vertical Depth: 3760 feet

Operator License No.: 5259
Op Name: MAI OIL OPERATIONS, INC.
Address: 8411 PRESTON RD STE 800
DALLAS, TX 75225

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3751		150 SX
SURF	8.625	219		160 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/14/2015 12:30 AM
Plug Co. License No.: 99977 Plug Co. Name: QUALITY OIL WELL CEMENTING
Proposal Rcvd. from: KENT WILLSON Company: MAI OIL OPERATIONS INC Phone: (785) 483-1676

Proposed Plugging Method: Ordered 300 sx 60/40 pozmix 4% gel cement, 13 sx gel and 500 # hulls.
PC at 1550' w/250 sx cement

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/14/2015 2:30 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Rigged to 5 1/2" casing with a swedge and pumped 75 sx cement w/300 # hulls mixed followed by 13 sx gel w/100 # hulls mixed in followed by 100 sx cement w/100 # hulls mixed in. Pumped to pressure with 500 psi. Shut in pressure 500 psi. Rigged to 8 5/8" casing and pumped 10 sx cement at 200 psi. Shut in pressure 200 psi.

GPS: 39.13022 -099.57375
GPS: 39.13022 -099.57375

Perfs:

Top	Bot	Thru	Comments
3678	3687		
3562	3565		
3546	3550		
3528	3531		
3508	3511		
3453	3457		

Remarks: QUALITY OILWELL CEMENTING TICKET # 3724

Plugged through: CSG

SEP 02 2015
OKM

District: 04

Signed [Signature]
(TECHNICIAN)

CM

KCC WICHITA

AUG 24 2015

RECEIVED

AUG 18 2015