

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-163-20353-00-00
Spot: N2NENW Sec/Twnshp/Rge: 15-10S-20W
4950 feet from S Section Line, 3300 feet from E Section Line
Lease Name: BRUEGGEMAN Well #: 11
County: ROOKS Total Vertical Depth: 3759 feet

Operator License No.:	String	Size	Depth (ft)	Pulled (ft)	Comments
<u>30606</u>	CIBP		3710		
Op Name: <u>MURFIN DRILLING CO., INC.</u>	PROD	4.5	3756		175 SX
Address: <u>250 N WATER STE 300</u> <u>WICHITA, KS 67202</u>	SURF	8.625	250		175 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 07/29/2015 8:30 AM
Plug Co. License No.: 30606 Plug Co. Name: MURFIN DRILLING CO., INC.
Proposal Rcvd. from: JOHN GERSTNER Company: MURFIN DRILLING CO., INC. Phone: (785) 421-2103

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement w/500 # hulls.
Port Collar at 1670' w/375 sx cement.
Squeezed at 1082' - 1113' w/50 sx cement and 1379' - 1410' w/65 sx cement.
Bridge plug at 3710'.
Production perforations: 3542' - 3659', 3756' - 3759' Arbuckle

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/29/2015 11:00 AM KCC Agent: PAT BEDORE

Actual Plugging Report:

Ran tubing to 3517' and pumped 75 sx cement w/200 # hulls. Pulled tubing to 2613' and pumped 100 sx cement w/200 # hulls. Pulled tubing to 1211' and pumped 100 sx cement to circulate cement to surface. Pulled all tubing and topped off 4 1/2" casing w/16 sx cement. Hooked to 8 5/8" x 4 1/2" annulus and pumped 8 sx cement. Shut in pressure 300 psi.
GPS: 39.18977N -099.54260W

Perfs:

Top	Bot	Thru	Comments
3756	3759		
3658	3659		
3639	3642		
3621	3625		
3542	3552		

Remarks: SWIFT SERVICES TICKET # 28717

Plugged through: TBG

SEP 02 2015 *CKM*

District: 04

Signed Pat Bedore
(TECHNICIAN) *CM*

Received
KANSAS CORPORATION COMMISSION

Form CP-2/3

JUL 30 2015

AUG 21 2015

CONSERVATION DIVISION
WICHITA, KS