

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-101-20137-00-00
Spot: NWSWSW Sec/Twnshp/Rge: 27-17S-27W
977 feet from S Section Line, 5050 feet from E Section Line
Lease Name: MUMMA Well #: B-1
County: LANE Total Vertical Depth: 4308 feet

Operator License No.: 5474
Op Name: NORTHERN LIGHTS OIL COMPANY, LL
Address: PO BOX 164
ANDOVER, KS 67002

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2096	0	WITH 400 SX CMT
SURF	8.625	286		WITH 225 SX CMT

Well Type: SWD UIC Docket No: D17744.0 Date/Time to Plug: 08/14/2015 9:00 AM
Plug Co. License No.: 31627 Plug Co. Name: WHITETAIL CRUDE, INC
Proposal Rcvd. from: PRESTON DREILING Company: Phone: (785) 639-2099

Proposed Plugging Method: RUN TBG TO BOTTOM & CIRCULATE CMT & HULLS TO SURFACE. PULL TBG & TOP OFF. TIE ONTO BACKSIDE & TRY TO PUMP 50 SX CMT IF POSSIBLE.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/14/2015 12:30 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

RUN TBG TO 1600' & PUMPED 105 SX CMT WITH 400# HULLS WITH 3% CC. CMT CIRCULATED TO SURFACE. PULLED TBG & TOPPED OFF WITH 25 SX CMT. TIED ONTO BACKSIDE & PUMPED 5 SX CMT. PRESSURED TO 300#.

Perfs:

Top	Bot	Thru	Comments
1786	1796		
1754	1774		
1706	1746		
1638	1678		
1606	1620		

Remarks: **COMPLIANCE ISSUE: FAILED MIT** USED 60/40 POZMIX 4% GEL 3% CC BY QUALITY SERVICES.

Plugged through: TBG

SEP 02 2015 ckm

District: 01

Signed Michael J Maier
MA
(TECHNICIAN)

RECEIVED
AUG 18 2015
KCC DODGE CITY

Received
KANSAS CORPORATION COMMISSION

Form CP-2/3

AUG 21 2015
CONSERVATION DIVISION
WICHITA, KS

UIC