

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-167-06705-00-01
Spot: SWNWSW Sec/Twnshp/Rge: 27-14S-13W
1671 feet from S Section Line, 4688 feet from E Section Line
Lease Name: HENRY REIN A Well #: 4
County: RUSSELL Total Vertical Depth: 2914 feet

Operator License No.: 30918
Op Name: NRD - REIN RESOURCES, A GENERAL
Address: 1165 DEL MAR COURT
UNION, KY 41091

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	6	2890		275 SX
SURF	10.75	381		250 SX

Well Type: EOR UIC Docket No: E09407.1 Date/Time to Plug: 07/28/2015 9:00 AM
Plug Co. License No.: 99977 Plug Co. Name: QUALITY OIL WELL CEMENTING
Proposal Revd. from: JUNIOR NEIL Company: NRD REIN RESOURCES Phone: (785) 445-2699

Proposed Plugging Method: Ordered 400 sx 60/40 pozmix 4% gel cement, 10 sx (1000 #) of gel, 600 # hulls.

Plugging Proposal Received By: RAY DINKEL WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/28/2015 1:30 PM KCC Agent: RAY DINKEL

Actual Plugging Report:

Perforated at 340', 680', 1250'.
Ran tubing to 2825' and pumped 8 sx = 800 # gel followed by 75 sx cement w/50 # hulls.
Pulled tubing to 1300' and pumped 100 sx cement w/100 # hulls. Cement circulated. POOH.
Topped off casing w/10 sx cement. Braden head was dug out and found to be full of cement.

GPS: 38.80303 -098.76003

Perfs:

Remarks: QUALITY CEMENTING TICKET # 1015

Plugged through: TBG

SEP 02 2015
CKM

District: 04

Signed

Ray A. Dinkel

(TECHNICIAN)

CM

Received
KANSAS CORPORATION COMMISSION

Form CP-2/3

AUG 03 2015

AUG 21 2015

CONSERVATION DIVISION
WICHITA, KS

✓UIC