

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-119-21341-00-00
Spot: SWNW Sec/Twnshp/Rge: 21-33S-30W
1980 feet from N Section Line, 660 feet from W Section Line
Lease Name: MEYER Well #: 1-21
County: MEADE Total Vertical Depth: 6400 feet

Operator License No.: 32211
Op Name: O'BRIEN ENERGY RESOURCES CORP.
Address: 18 CONGRESS ST, STE 207
PORTSMOUTH, NH 03801

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		5750		
PROD	4.5	6370	2601	WITH 180 SX CMT
SURF	8.625	1495		WITH 550 SX CMT

Well Type: OG UIC Docket No: _____ Date/Time to Plug: 08/07/2015 10:30 AM
Plug Co. License No.: 32833 Plug Co. Name: SARGENT LILLARD CASING PULLING, INC.
Proposal Rcvd. from: JOHN SCHOOLCRAFT Company: SARGENT LILLARD CASING PULL Phone: (580) 254-1881

Proposed Plugging Method: PUMP 100# HULLS & 25 SX CMT. PLUG AT 1540' WITH 50 SX CMT. PLUG AT 550' WITH 50 SX CMT. PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: KEN JEHLIK Witness Type: NONE
Date/Time Plugging Completed: 08/07/2015 4:45 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

PUMP 25 SX CMT WITH 100# HULLS. DISPLACE TO 3950' & PRESSURE UP. HOLDING. 1ST PLUG AT 1530' WITH 50 SX CMT. 2ND PLUG AT 550' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5798	5808		
4430	4436		

Remarks: USED COMMON CEMENT BY SARGENT LILLARD.

Plugged through: CSG

SEP 02 2015 *ckm*

District: 01

Signed *Ken Jehlik*
(TECHNICIAN)

RECEIVED
AUG 24 2015
KCC DODGE CITY *MP*

KCC WICHITA Form CP-2/3
AUG 26 2015
RECEIVED