

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-095-30046-00-00
Spot: NWNE Sec/Twnshp/Rge: 1-30S-8W
4620 feet from S Section Line, 1980 feet from E Section Line
Lease Name: GWYNN-RENDER Well #: 2
County: KINGMAN Total Vertical Depth: 4544 feet

Operator License No.: 5123
Op Name: PICKRELL DRILLING COMPANY, INC.
Address: 100 S MAIN STE 505
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	4538		150 SX
SURF	8.625	214		150 SX

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 08/17/2015 12:00 AM
Plug Co. License No.: 31925 Plug Co. Name: QUALITY WELL SERVICE, INC.
Proposal Rcvd. from: JACK GURLEY Company: QUALITY WELL SERVICE Phone: _____

Proposed Plugging Method: AS PER KCC RULES & REGS

Plugging Proposal Received By: STEVE VANGIESON WitnessType: PARTIAL
Date/Time Plugging Completed: 08/17/2015 4:00 PM KCC Agent: B. J. HOPE

Actual Plugging Report:

SET CIBP @ 4100' CAPPED WITH 2 SX CEMENT ON TOP. TESTED CAISNG TO 300 LBS. PERFORATED @ 1150' WITH 4 SHOTS, PUMPED 35 SX OF CLASS A 3% CEMENT AND DISPLACED TO 1100'. CASING WAS SQUEEZED AT 690' WITH 150 SX OF CEMENT IN APRIL OF 1990, PRESSURE TEST CASING TO 300 LBS HELD, PERFORATED @ 265' PUMPED 130 SX OF CLASS A CEMENT WITH NO CIRCUALTION. 8/17/15 CUT HEAD OFF, TAG INSIDE OF SURFACE @ 15', TAGGED CEMENT INSIDE 4.5" DRY, @ 245'. FILLED 4.5" WITH 70 SX OF CEMENT AND 5 SX INSIDE SURFACE.

Perfs:

Top	Bot	Thru	Comments
4125	4143	CSG	

Remarks: QUALITY WELL SERVICE PROVIDED CEMENT FOR THIS JOB ALS, TICKET #6367.

Plugged through: CSG

SEP 02 2015
ELM

District: 02

Signed _____

B. J. Hope

(TECHNICIAN)
KCC WICHITA

AUG 28 2015

RECEIVED

Form CP-2/3

JK