

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-133-26643-00-00
Spot: NESW Sec/Twnshp/Rge: 17-27S-21E
1980 feet from S Section Line, 1980 feet from W Section Line
Lease Name: SMITH, JOSEPH A. Well #: 17-1
County: NEOSHO Total Vertical Depth: 954 feet

Operator License No.: 33343
Op Name: POSTROCK MIDCONTINENT PRODUC
Address: OKLAHOMA TOWER 210 PARK AVE.
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comment
PROD	4.5	948		100 SX
SURF	8.625	22		4 SX

Well Type: CM UIC Docket No: _____ Date/Time to Plug: 06/22/2015 8:00 AM
Plug Co. License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC
Proposal Rcvd. from: KEN PAULIE Company: POSTROCK MIDCONTINENT Phone: (620) 432-4200

Proposed Plugging Method: RUN TUBING TO WELL TD, CEMENT THROUGH TUBING TO SURFACE, PULL TUBING OUT OF HOLE AND TOP WELL OFF WITH CEMENT.

Plugging Proposal Received By: ALAN DUNNING WitnessType: NONE
Date/Time Plugging Completed: 06/22/2015 5:00 PM KCC Agent: ALAN DUNNING

Actual Plugging Report:

A 2.375 inch cement string was ran to 950 ft and 56 sacks of cement pumped. The cement string was pulled to 500 ft and 48 sacks of cement pumped. The cement string was pulled to 200 ft and 7 sacks of cement pumped. The cement string was removed and the well topped off with 3 sacks of cement. A total of 114 sacks of portland cement were used to plug well. The well was cut off below plow depth and the location restored.

Perfs:

Top	Bot	Thru	Comments
866	870		
812	814		
806	809		

RECEIVED
KCC DIST # 3
AUG 25 2015
CHANUTE, KS

AD

Remarks:

Plugged through: TBG

District: 03

Signed

Alan Dunning
KCC WICHITA

(TECHNICIAN)

AUG 28 2015

RECEIVED

SEP 02 2015
CKM
Form CP-2/3