

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-205-23996-00-01
Spot: SENENW Sec/Twnshp/Rge: 10-28S-17E
3960 feet from S Section Line, 2805 feet from E Section Line
Lease Name: KEPLEY Well #: 10-9
County: WILSON Total Vertical Depth: 984 feet

Operator License No.: 33343
Op Name: POSTROCK MIDCONTINENT PRODUC
Address: OKLAHOMA TOWER 210 PARK AVE.
OKLAHOMA CITY, OK 73102

String	Size	Depth (ft)	Pulled (ft)	Comment
CIBP		810		
PROD	4.5	981		0 SX
SURF	0	0		0 SX

Well Type: CM UIC Docket No: _____ Date/Time to Plug: 04/23/2015 8:00 AM
Plug Co. License No.: 33749 Plug Co. Name: KEPLEY WELL SERVICE, LLC
Proposal Rcvd. from: KEN PAULIE Company: POSTROCK MIDCONTINENT Phone: (620) 432-4200

Proposed Plugging Method: RUN TUBING TO WELL TD, CEMENT THROUGH TUBING TO SURFACE, PULL TUBING OUT AND TOP WELL OFF WITH CEMENT.

Plugging Proposal Received By: RUSSELL HINE WitnessType: NONE
Date/Time Plugging Completed: 04/23/2015 8:00 AM KCC Agent: ALAN DUNNING

Actual Plugging Report:

A 2.375 inch cement string was ran to 798 ft inside the production string and 35 sacks of cement pumped. The cement string was pulled to 350 ft and 28 sacks of cement pumped. The cement string was removed and the well topped off with 10 sacks. A total of 73 sacks of portland cement were used to plug well. The well was cut off below plow depth and the location restored.

Perfs:

Top	Bot	Thru	Comments
730	736		
716	726		

RECEIVED
KCC DIST # 3
AUG 26 2015
CHANUTE, KS

AD

Received
KANSAS CORPORATION COMMISSION

AUG 31 2015

CONSERVATION DIVISION
WICHITA, KS

SEP 02 2015
CKM

Remarks:

Plugged through: CSG

District: 03

Signed Alan Dunning
(TECHNICIAN)