

1-030228

15-097-30098-0001

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-Not Available

SE NW, SEC. 33, T. 27 S, R. 20 W
1980 FSL feet from ~~NW~~ SE Corner of section line
1980 FEL feet from ~~NW~~ SE Corner of section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6743

Lease Name Brensing "A" Well # 1

Operator: Southwind Petroleum, Corp.
Name & Address: 1825 West 13th Street
Wichita, KS 67203

County Kiowa

Well Total Depth 4970 161.53 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 635

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Kelso Casing Pulling License Number 6050

Address Box 347, Chase, KS 67524

Company to plug at: Hour: 1:00 pm Day: 17 Month: July Year: 19 84

Plugging proposal received from Bob Brenneman

(company name) Kelso (phone) 316-938-2457

were: 4 1/2" set at 4966' Perfs 4896-97'

1st plug pump 35 sx cement to bottom

2nd plug pump 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, release 8 5/8" rubber plug and pump an additional 150 sx cement.

Plugging Proposal Received by Steve Rement (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 3:30 pm Day: 18 Month: July Year: 19 84

ACTUAL PLUGGING REPORT 4 1/2" set at 4966' Perfs 4896-97'

1st plug pumped 35 sx cement to bottom, 2nd plug pumped 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, released 8 5/8" rubber plug and pumped an additional 150 sx cement.

After 50 sx on last plug - broke out of surface pipe. Next day, re-entered well with tubing 1st plug at 650' with 50 sx cement

2nd plug circulated cement from 270' to surface with 80 sx cement'

Remarks: They recovered 2539' of 4 1/2" casing. Used 60/40 Pozmix by Allied.
(If additional description is necessary, use BACK of this form)

RECEIVED
STATE CORPORATION COMMISSION
JUL 24 1984
CONSERVATION DIVISION
Wichita, Kansas

INVOICED

DATE 7-31-84

Signed Steve Rement (TECHNICIAN)

INV. NO. 2768
7-18