

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-097-20420-00-01
Spot: SESENE Sec/Twnshp/Rge: 33-27S-20W
2970 feet from S Section Line, 330 feet from E Section Line
Lease/Unit Name: CATE Well Number: 1
County: KIOWA Total Vertical Depth: 4900 feet

Operator License No.: 5414 Conductor Pipe: Size feet: 3159.25
Op Name: RICHARDSON, J. MARK/RICHARDSON OIL OPERATING Surface Casing: Size 8.625 feet: 602 WITH 400 SX CMT
Address: 2843 KEYWEST CT. Production: Size 4.5 feet: 4900 WITH 125 SX CMT
WICHITA, KS 67204 Liner: Size feet:

Well Type: SWD UIC Docket No: D27677.1 Date/Time to Plug: 05/01/2002 9:00 AM
Plug Co. License No.: 32923 Plug Co. Name: RICHARDSON, TERRY DBA TR SERVICES
Proposal Rcvd. from: LARRY MITCHELL Company: J MARK RICHARDSON Phone: (316) 838-4242

Proposed Plugging Method: SAND TO 4829' & 4 SX CMT WITH BAILER. 1ST PLUG AT 1250' WITH 50 SX CMT. 2ND PLUG AT 650' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: SCOTT ALBERG Witness Type: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 05/01/2002 10:30 AM KCC Agent: SCOTT ALBERG

Actual Plugging Report:

PBTD 4898'. PERFS AT 4879-4890'. LEFT PACKER IN HOLE @ 4700'. SAND BACK TO 4650', DUMP 4 SX CMT ON TOP WITH BAILER. 1ST PLUG SPOT 10 SX GEL & 50 SX CMT AT 1250'. 2ND PLUG SPOT 50 SX CMT @ 620'. 3RD PLUG TOP OFF WITH 10 SX CMT AT 0-40'. GOOD CIRCULATION ON JOB.

RECEIVED
MAY 03 2002
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 800' OF 4 1/2" CASING.

Plugged through: CSG

District: 01

Signed


(TECHNICIAN)

INVOICE # MAY 02 2002

DATE 5-6-02

INV. NO. 2002061742

