

1090997

TO: STATE CORPORATION COMMISSION

5-20

API NUMBER ²⁰⁷⁴⁴ 15-097-21,744-0000
NW NW SE SEC. 34, T 27 S, R 20 W

CONSERVATION DIVISION - PLUGGING SECTION 2310 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 2310 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME MCFADDEN C WELL # 1

TECHNICIAN'S PLUGGING REPORT

COUNTY KIOWA 158.60

OPERATOR LICENSE # 5414

WELL TOTAL DEPTH 4880 FEET

OPERATOR: J. MARK RICHARDSON PRODUCTION CSG: SIZE 4 1/2" @ 4879' WITH 200 SX

NAME AND 2843 KEYWEST CT. SURFACE CASING: SIZE 8 5/8" @ 604' WITH 425 SX

ADDRESS WICHITA, KS 67204

ABANDONED OIL WELL GAS WELL INPUT WELL SWD WELL D/A

OTHER WELL AS HEREINAFTER INDICATED

PLUGGING CONTRACTOR ALLIED CEMENTING LICENSE NUMBER NA

ADDRESS PO BOX 31, RUSSELL, KS 67665-0031

COMPANY TO PLUG AT: HOUR: 10:15 AM DAY: 20 MONTH: 05 YEAR: 1999

PLUGGING PROPOSAL RECEIVED FROM CARL SHIELD

(COMPANY NAME) ALLIED CEMENTING (PHONE) 785-483-2627

WERE: PERFS AT 4864-4870

SAND TO 4800' WITH 4 SX CEMENT ON TOP. ALLIED PUMPED 3 HULLS, 10 SX GEL, 50 SX CEMENT, 10

SX GEL, 1 HULL, 8 5/8" WIPER PLUG, 150 SX CEMENT. PRESSURE AT 700#. SHUT IN WITH 300#.

PLUGGING PROPOSAL RECEIVED BY STEVE MIDDLETON

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL PART NONE

OPERATIONS COMPLETED: HOUR: 11:15 AM DAY: 20 MONTH: 05 YEAR: 1999

ACTUAL PLUGGING REPORT

SAND TO 4800' WITH 4 SX CEMENT ON TOP. ALLIED PUMPED 3 HULLS, 10 SX GEL, 50 SX CEMENT,

10 SX GEL, 1 HULL, 8 5/8" WIPER PLUG, 150 SX CEMENT. PRESSURE AT 700#. SHUT IN WITH 300#.

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2486' OF 4 1/2" CASING.
(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING. STATE CORPORATION COMMISSION

INVOICED

MAY 24 1999
5-24-99

SIGNED [Signature] (TECHNICIAN) FORM CP-2/3

DATE 5-25-99
INV. NO. 60984

CONSERVATION DIVISION
Wichita, Kansas

[Handwritten signature]