

To: 1 041208
STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15-097-20,603-0000

SW SW NE, SEC. 34, T 27 S, R 20 W/X

2970 feet from S section line

2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License / 5414

Operator: J. Mark Richardson

Name: 155 N. Market, #840

Address: Wichita, KS 67202

Lease Name Brensing B Well # 1

County Kiowa 158.76

Well Total Depth 4885 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 582

Abandoned Oil Well Gas Well X Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Greensburg Well Service License Number 31201

Address 303 E. Kansas, Greensburg, KS 67054

Company to plug at: Hour: 11 a.m. Day: 1 Month: 10 Year: 19 96

Plugging proposal received from Carl Schield

(company name) Greensburg Well Service (phone) 316-723-2204

Perfs: 4 1/2" at 4884', Perfs at 4877-82, 4886-89, 4804-67'

1st plug sand back to 4760' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, release 8 5/8" wiper plug and pump 150 sx cement.

Plugging Proposal Received by Kevin Strube (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 11:45 a.m. Day: 1 Month: 10 Year: 19 96

ACTUAL PLUGGING REPORT 1st plug sanded back to 4760' and dumped 4 sx cement on top of sand

bridge through bailer,

2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 50 sx cement,

10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 150 sx cement.

Maximum pressure 400 psi and shut in 100 psi.

10-4-97

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2525' of 4 1/2" casing.

(if additional description is necessary, use BACK of this form.)

INVOICED

DATE 10-10-96

INV. NO. 46681

Signed Stephen J. Pfeifer (TECHNICIAN)