

To: 1 040401
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

1-30 394
API NUMBER 15- 097-20,556-0000
C SW NW, SEC. 34, T 27 S, R 20 W&E

TECHNICIAN'S PLUGGING REPORT

Operator License # 5414

Operator: J. Mark Richardson
Name & Address 155 North Market, Suite 840
Wichita, KS 67202

3300 feet from S section line
4620 feet from E section line

Lease Name McFadden B Well # 1
County Kiowa 158.60

Well Total Depth 4880 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 598

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor J. Mark Richardson License Number 5414

Address 155 North Market, Suite 840, Wichita, KS 67202

Company to plug at: Hour: 9:30 a.m. Day: 30 Month: 1 Year: 19 90

Plugging proposal received from Carl Schield

(company name) J. Mark Richardson (phone) 316-262-3192

were: 4 1/2" at 4879' PBTD 4877' Perfs at 4873-76, 4863-69'

1st plug sand back to 4790' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 4 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 140 sx cement.

Plugging Proposal Received by Richard Lacey
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 11 a.m. Day: 30 Month: 1 Year: 19 90

ACTUAL PLUGGING REPORT Previous plugging attempt-Pumped 3 sx hulls, 10 sx gel, 15 sx cement, and hole developed in surface pipe. Must plug through tubing. Richard Lacey witnessed Moved in rig and washed hole down to good cement at 756'.

1st plug sanded back to 4790' and dumped 4 sx cement on top of sand through bailer

Spotted plugs through 2 3/8" tubing and pumped 10 sx gel ahead of 1st plug

2nd plug at 756' with 30 sx cement, 3rd plug at 600' with 50 sx cement,

4th plug at 40' with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan. Recovered 2712' of 4 1/2" casing
(If additional description is necessary, use BACK of this form.)

observe this plugging.

INVOICED
DATE 2-13-90
INV. NO. 27422
1-30

Signed Stephen J. Pfeifer
(TECHNICIAN)

RECEIVED
STATE CORPORATION COMMISSION
FEB 7 1990
CONSERVATION DIVISION
Wichita, Kansas