

1 010129

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- N/A  
NE NE SW, SEC. 34, T 27 S, R 20 <sup>W/E</sup>

TECHNICIAN'S PLUGGING REPORT

Operator License # 5414  
Operator: J. Mark Richardson  
Name & Address: 640 Century Plaza Building  
Wichita, KS 67202

2310 feet from S section line  
2970 feet from E section line  
Lease Name McFadden Well # A-2  
County Kiowa 158.76  
Well Total Depth 4885 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 583

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling License Number 6050  
Address P. O. Box 347, Chase, KS 67524

Company to plug at: Hour: 10:15 am Day: 2 Month: May Year: 19 86

Plugging proposal received from Roger Lust  
(company name) Kelso (phone) 316-938-2457

were: 4 1/2" at 4885' Perfs at 4868-70'  
1st plug sand back to 4810' and dump 4 sx cement on top of sand through bailer  
2nd plug squeeze well with 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls,  
release 8 5/8" rubber plug and pump 150 sx cement.

Plugging Proposal Received by Richard W. Lacey  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_  
Operations Completed: Hour: 11:45 am Day: 2 Month: May Year: 19 86

ACTUAL PLUGGING REPORT 1st plug sanded back to 4810' and dumped 4 sx cement on top of  
sand through bailer, 2nd plug squeezed well with 3 sx hulls, 10 sx gel, 50 sx cement, 10  
sx gel, 1 sack hulls and 150 sx cement. There was water in hole - could not get plug  
container in.

Maximum pressure 700 psi and shut in 600 psi

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. Recovered 3000' 4 1/2" casing  
(If additional description is necessary, use BACK of this form.)

**INVOICED**  
MAY 12 1986

DATE \_\_\_\_\_  
INV. NO. 13791

Signed Jack R. Lacey  
(TECHNICIAN) SQ

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 12 1986  
CONSERVATION DIVISION  
Wichita, Kansas