

1041403

TO: STATE CORPORATION COMMISSION

API NUMBER 15-097-21,153-0000
S/2 SE SW SEC. 22, T 27 S, R 19 W

CONSERVATION DIVISION - PLUGGING SECTION 330 FEET FROM SOUTH SECTION LINE

WICHITA STATE OFFICE BLDG., 130 S. MARKET 3300 FEET FROM EAST SECTION LINE

WICHITA, KANSAS 67202

LEASE NAME BRENSING "A" WELL # 3

TECHNICIAN'S PLUGGING REPORT

COUNTY KIOWA 158.44

OPERATOR LICENSE # 5118 6/29 WELL TOTAL DEPTH 4875 FEET

OPERATOR: TGT PETROLEUM CORPORATION PRODUCTION CSG: SIZE 5 1/2" @ 4874' WITH 250 SX

NAME AND 7570 W 21ST BLDG 1010 STE D SURFACE CASING: SIZE 8 5/8" @ 481' WITH 300 SX

ADDRESS WICHITA, KS 67205

ABANDONED OIL WELL GAS WELL INPUT WELL INJ WELL D/A

OTHER WELL AS HEREINAFTER INDICATED _____

PLUGGING CONTRACTOR MIKE'S TESTING & SALVAGE, INC LICENSE NUMBER 31529

ADDRESS PO BOX 467, CHASE, KS 67524-0209

COMPANY TO PLUG AT: HOUR: 10:45 AM DAY: 29 MONTH: 06 YEAR: 2000

PLUGGING PROPOSAL RECEIVED FROM HAROLD BELLERIVE

(COMPANY NAME) MIKE'S TESTING & SALVAGE (PHONE) 316-938-2945

WERE: PERFS AT 4840-42, CIBP @ 4870

1ST PLUG CIBP AT 4400' AND PUT 5 SX CEMENT ON TOP OF CIBP THROUGH DUMP BAILER. LOAD HOLE

WITH GEL. SPOT PLUGS THROUGH 5 1/2" CASING. 2ND PLUG AT 1270' WITH 50 SX CEMENT.

3RD PLUG AT 510' WITH 50 SX CEMENT. 4TH PLUG AT 40' WITH 10 SX CEMENT.

PLUGGING PROPOSAL RECEIVED BY STEVE PFEIFER

PLUGGING OPERATIONS ATTENDED BY AGENT?: ALL PART NONE

OPERATIONS COMPLETED: HOUR: 12:15 PM DAY: 29 MONTH: 06 YEAR: 2000

ACTUAL PLUGGING REPORT _____

1ST PLUG CIBP AT 4400' AND PUT 5 SX CEMENT ON TOP OF CIBP THROUGH DUMP BAILER. LOAD HOLE

WITH GEL. SPOT PLUGS THROUGH 5 1/2" CASING. 2ND PLUG AT 1270' WITH 50 SX CEMENT.

3RD PLUG AT 510' WITH 50 SX CEMENT. 4TH PLUG AT 40' WITH 10 SX CEMENT.

REMARKS: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 3000' OF 5 1/2" CASING.

(IF ADDITIONAL DESCRIPTION IS NECESSARY, USE BACK OF THIS FORM.)

I (DID) OBSERVE THIS PLUGGING _____ STATE CORPORATION COMMISSION

RECEIVED
INVOICED

SIGNED Stephen J. Pfeifer
(TECHNICIAN) FORM CP-2/3

DATE 7/18/00 JUL 14 2000

WV. NO. 1060078 CONSERVATION DIVISION
Wichita, Kansas