

To: 1 060156 2-6
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-097-21,344-0000
C SE NW, SEC. 22, T. 27 S, R. 19 W/E
1980' feet from N&S section line
1980' feet from W&E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 5118
Operator: TGT Petroleum Corporation
Name & Address: 209 E. William, Ste. 615
Wichita, KS 67202

Lease Name Gordon Well # 1
County Kiowa
Well Total Depth 4900 159.25 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 543

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X
Other well as hereinafter indicated _____

Plugging Contractor Brandt Drilling License Number 5840
Address 200 W. Douglas, Ste. 700, Wichita, KS 67202

Company to plug at: Hour: 12:15 p.m. Day: 6 Month: 2 Year: 19 93

Plugging proposal received from Merlin Freeman
(company name) Brandt Drilling (phone) 316-267-4335

Work: to fill hole with heavy mud and spot cement through drill pipe Anhydrite 1243'
1st plug at 1275' with 50 sx cement, 2nd plug at 600' with 60 sx cement,
3rd plug at 40' with 10 sx cement,
4th plug to circulate rathole with 15 sx cement,
5th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Case Morris
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None RECEIVED
Operations Completed: Hour: 6 p.m. Day: 6 Month: 2 Year: 19 93

ACTUAL PLUGGING REPORT 1st plug at 1275' with 50 sx cement,
2nd plug at 600' with 60 sx cement,
3rd plug at 40' with 10 sx cement,
4th plug to circulate rathole with 15 sx cement,
5th plug to circulate mousehole with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton.
(If additional description is necessary, use BACK of this form.)

INVOICED
I (X) did not observe this plugging.

DATE 2-17-93 Signed Case Morris
(TECHNICIAN)

INV. NO. 37369
2-6

Expected Spud Date 11 month 1 day 92 year

Section 35 NW Sec 22 Twp 27 S Rg 19 X

OPERATOR: License # 5118 Name: TGT. Petroleum Corp Address: 209 E. William #615 City/State/Zip: Wichita, Ks 67202 Contact Person: B. Lynn Herrington Phone: 262-6489

1980 feet from North line of Section 1980 feet from West line of Section IS SECTION X REGULAR IRREGULAR

(NOTE: Locate well on the Section Plat on Reverse Side County: Kiowa

CONTRACTOR: License #: 5840 Name: Brandt Drilling

Lease Name: GORDON Well #: 1 Field Name: Quaker South

Is this a Prorated/Spaced Field? yes X no Target Formation(s): Mississippi

Well Drilled For: Oil Gas OUVO Seismic Other Well Class: Enh Rec Storage Disposal of Holes Infield Pool Ext Wildcat Other Type Equipment: Mud Rotary Air Rotary Cable

Nearest lease or unit boundary: 660 Ground Surface Elevation: 2235 feet

Water well within one-quarter mile: yes X Public water supply well within one mile: yes X

Depth to bottom of fresh water: 210 Depth to bottom of usable water: 550

Surface Pipe by Alternates: X 1 2 Length of Surface Pipe Planned to be set: 440

Length of Conductor pipe required: None Projected Total Depth: 4900 Formation at Total Depth: Mississippi

Directional, Deviated or Horizontal wellbore? yes X no If yes, true vertical depth: Bottom Hole Location: Exp. 5/13/93

Water Source for Drilling Operations: well farm pond et DER Permit #: Will Cores Be Taken? yes X no

If yes, proposed zone: Alt. IReq.

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 101, et. seq. It is agreed that the following minimum requirements will be met:

Pusher: Mark Green SPUD DATE: 1-22-93 INIT. S.P. LENGTH SURFACE PLANNED: 532 to 888" RESERVE PIT STATUS: REMOVE FLUID LINED after salt sect. bbls. when done bbls. RATHOLED AHEAD? Y N SIZE HOLE SURFACE PIPE 8 3/4 @ 543 CONDUCTOR ANHYDRITE T- B-1243 ELEVATION TD 4900 FORMATION RAN PIPE @ DV TOOL ALT II DONE SX Y N Arbuckle Plug @ Ft. W/ SX Hug./Council @ Ft. W/ SX Anhydrite Base @ 1275 Ft. W/ 50 SX 1/2 Base Anyh. @ Ft. W/ SX 1/2, 1/2 Plug @ Ft. W/ SX Bottom Surface @ 600 Ft. W/ 60 SX 40' Plug @ 40 Ft. W/ 10 SX RAT HOLE CIRC/W 15 SX MOUSE HOLE W/ 10 SX WATER WELL SX (Irr. Well Pond Hauling) TECHNICIAN DATE 2-5-93 TYPE OF CEMENT 60/40 67. STARTING TIME 11 (AM/PM) DATE 26-93 COMPLETE TIME 9 (AM/PM) DATE 26-93 CEMENT COMPANY Halliburton