

To: 1090632
STATE CORPORATION COMMISSION
Wichita State Office Bldg. PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15-097-20,623-0000
SW SW SW, SEC. 4, T 27 S, R 20 W/E

TECHNICIAN'S PLUGGING REPORT
Operator License # 8061
Operator: Oil Producers, Inc. of Kansas
Name & Address: P.O. Box 8647
Wichita, KS 67208

330 feet from S section line
4950 feet from E section line
Lease Name Einsel H Well # 1
County Kiowa 160.55
Well Total Depth 4940 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 615

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor D S & W Well Servicing, Inc. License Number 6901
Address: P.O. Box 231, Claflin, KS 67525

Company to plug at: Hour: 4:50 p.m. Day: 5 Month: 12 Year: 1995

Plugging proposal received from Kent Strube
(company name) D S & W Well Servicing, Inc. (phone) 316-587-3361

Work: 4 1/2" at 4938' w/175 sx cement, PBTD 4858', Perfs at 4844-46'
1st plug sand back to 4800' and dump 4 sx cement on top of sand through bailer,
2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"
wiper plug and pump 150 sx cement.

Plugging Proposal Received by Steve Middleton
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 5:30 p.m. Day: 5 Month: 12 Year: 1995

ACTUAL PLUGGING REPORT 1st plug sanded back to 4800' and dumped 4 sx cement on top of
sand through bailer,

2nd plug pumped 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, released 8 5/8"
wiper plug and pumped 150 sx cement.

Maximum pressure 490 psi and shut in 300 psi.

Remarks: Used 60/40 Pozmix 6% gel by Halliburton. Recovered 2475' of 4 1/2" casing.
(if additional description is necessary, use BACK of this form.)

INVOLVED (copy to be observed this plugging.)

DATE 12-13-95
INV. NO. 44338

12-7-95 DEC - 7 1995
SIGNED _____
(TECHNICIAN)