

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-039-20237-00-01
Spot: NENW Sec/Twnshp/Rge: 22-1S-26W
660 feet from N Section Line, 1980 feet from W Section Line
Lease Name: RICHARDS Well #: 1
County: DECATUR Total Vertical Depth: 3565 feet

Operator License No.: 32457
Op Name: ABERCROMBIE ENERGY, LLC
Address: 10209 W. CENTRAL, STE 2
WICHITA, KS 67212

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	1931		300 SX
SURF	8.625	233		160 SX

Well Type: WSW UIC Docket No: _____ Date/Time to Plug: 08/13/2015 10:00 AM
Plug Co. License No.: 32592 Plug Co. Name: WILD WEST WELL SERVICE, INC.
Proposal Rcvd. from: GARY MISAK Company: ABERCROMBIE ENERGY LLC Phone: (316) 262-1841

Proposed Plugging Method: Ordered 200 sx 60/40 pozmix 4% gel cement w/300 # hulls.
8 5/8" surface casing set at 233' w/160 sx cement. 4 1/2" production casing set at 1931' w/300 sx cement. TD 3565', PBD 1816'.
Perforations at 1620' - 1670'.

Plugging Proposal Received By: CASE MORRIS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/13/2015 12:00 PM KCC Agent: DARREL DIPMAN

Actual Plugging Report:

Ran tubing to 1574' and pumped 120 sx cement w/300 # hulls. CWC. Pulled tubing to surface. Connected to 4 1/2" casing and pumped 5 sx cement. Connected to 8 5/8" surface casing and pumped 15 sx cement. Pressure to 200 psi.

GPS: 39.95605N -100.22797W

Perfs:

Top	Bot	Thru	Comments
1620	1670		

Remarks: CONSOLIDATED OIL WELL SERVICES TICKET # 49,477

Plugged through: TBG

9/2/15 ckm

District: 04

Signed Darrel Dipman
(TECHNICIAN) CM

KCC WICHITA

Form CP-2/3

AUG 18 2015
AUG 18 2015

AUG 28 2015
RECEIVED