

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-051-26588-00-00
Spot: E2SWSESE Sec/Twnshp/Rge: 7-15S-16W
330 feet from S Section Line, 900 feet from E Section Line
Lease Name: BRUNGARDT Well #: 1
County: ELLIS Total Vertical Depth: 3600 feet

Operator License No.: 34369
Op Name: AMERICAN LAND AND ENERGY LLC
Address: 7277 TENBY WAY
CASTLE PINES, CO 80108

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	5.5	3569	2050	200 SX
SURF	8.765	1050		425 SX

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/18/2015 8:30 AM
Plug Co. License No.: 32810 Plug Co. Name: PROFESSIONAL PULLING SERVICES LLC
Proposal Rcvd. from: GARY LEIKER Company: AMERICAN LAND AND ENERGY Phone: (303) 358-9938

Proposed Plugging Method: Ordered 350 sx 60/40 pozmix 4% gel cement w/500 # hulls.
Alt I complete.
KC perforations: 3218' - 3222'
CIBP over Arb.

Plugging Proposal Received By: PAT STAAB Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/18/2015 6:30 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Washed out sand to 2560' Pumped 10 sx cement and displaced top of sand. Cut casing at 2050'. Pulled casing to 1670'. Rigged to casing and pumped 165 sx cement w/300 # hulls. Pulled casing to 1039' and pumped 50 sx cement w/100 # hulls. Pulled casing to 450' and pumped 115 sx cement w/100 # hulls to circulate cement to surface. Pulled casing. Hole standing full.

GPS: 38.75589 -099.13742

Perfs:

Top	Bot	Thru	Comments
3450	3454		
3437	3441		
3400	3404		
3286	3294		
3274	3278		
3264	3268		
3234	3238		
3218	3222		

Remarks: GLOBAL CEMENTING TICKET # 2503

Plugged through: CSG

District: 04

Signed _____

(TECHNICIAN)

CM

AUG 20 2015

KCC WICHITA

AUG 28 2015

RECEIVED

Form CP-2/3