

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS. 67202-1513

API Well Number: 15-101-22567-00-00
Spot: SESWNESE Sec/Twnshp/Rge: 14-16S-28W
1617 feet from S Section Line, 680 feet from E Section Line
Lease Name: LAWRENCE Well #: 1-14
County: LANE Total Vertical Depth: 4640 feet

Operator License No.: 6569
Op Name: CARMEN SCHMITT, INC.
Address: PO BOX 47
GREAT BEND, KS 67530

String	Size	Depth (ft)	Pulled (ft)	Comments
SURF	8.625	220		WITH 150 SX CMT

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 08/08/2015 11:30 PM
Plug Co. License No.: 31548 Plug Co. Name: DISCOVERY DRILLING
Proposal Rcvd. from: TOM ALM Company: DISCOVERY DRILLING Phone: (785) 623-2920

Proposed Plugging Method: 1ST PLUG AT 2160' WITH 50 SX CMT. 2ND PLUG AT 1410' WITH 80 SX CMT. 3RD PLUG AT 720' WITH 50 SX CMT. 4TH PLUG AT 270' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Plugging Proposal Received By: ERIC MACLAREN Witness Type: NONE
Date/Time Plugging Completed: 08/09/2015 1:30 AM KCC Agent: ERIC MACLAREN

Actual Plugging Report:

Perfs:

1ST PLUG AT 2160' WITH 50 SX CMT. 2ND PLUG AT 1410' WITH 80 SX CMT. 3RD PLUG AT 720' WITH 50 SX CMT. 4TH PLUG AT 270' WITH 50 SX CMT. 5TH PLUG AT 60' WITH 20 SX CMT. 6TH PLUG TO CIRCULATE RAT HOLE WITH 30 SX CMT. 7TH PLUG TO CIRCULATE MOUSE HOLE WITH 20 SX CMT.

Remarks: USED 60/40 POZMIX 4% GEL 1/4# FLO SEAL BY QUALITY OIL WELL.

Plugged through: DP

SEP 02 2015 *apm*

District: 01

Signed *Eric MacLaren*

(TECHNICIAN)

RECEIVED
AUG 24 2015
KCC DODGE CITY *MR*

KCC WICHITA Form CP-2/3
AUG 26 2015
RECEIVED