

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-055-10117-00-01
Spot: NENW Sec/Twnshp/Rge: 19-26S-34W
4504 feet from S Section Line, 2987 feet from E Section Line
Lease Name: PLEASANT PRAIRIE UNIT Well #: 6
County: FINNEY Total Vertical Depth: 5153 feet

Operator License No.: 34997
Op Name: CASILLAS PETROLEUM CORP
Address: 401 S. BOSTON AVE. SUITE 2400
TULSA, OK 74103

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3833		
DVT		2797		WITH 200 SX CMT
PROD	5.5	5152	0	WITH 450 SX CMT
SURF	8.625	805		WITH 425 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/17/2015 10:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: KENT PENDERGRAFT Company: CASILLAS PETROLEUM Phone: (620) 287-4060

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: KEN JEHLIK Witness Type: NONE
Date/Time Plugging Completed: 08/19/2015 1:00 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

RBP @ 4800'. PACKER AT 4248'. PERFS AT 4476'-4478' WERE CEMENT SQUEEZED WITH 150 SX CMT. LEFT 75 SX CMT IN THE CASING & TBG. TOP OF TBG FISH & CMT IS 3891'. PACKER & RBP LEFT IN HOLE. PERFORATE AT 775'. RUN TBG TO 1857' & SPOT 20 SX CMT. TOOH WITH TBG. HOOK UP TO 5 1/2" CASING AND CIRCULATE CMT TO SURFACE THROUGH PERFS AT 775' LEAVING THE CASING & ANNULUS FULL OF CMT.

Perfs:

Top	Bot	Thru	Comments
5027	5110		

Remarks: **COMPLIANCE ISSUE: DENIED TA HIGH FL** USED 60/40 POZMIX 4% GEL BY ALLIED.


Plugged through: TBG

SEP 02 2015
CKM

District: 01

RECEIVED
AUG 24 2015

Signed



(TECHNICIAN)

KCC WICHITA

KCC DODGE CITY

AUG 26 2015

Form CP-2/3

RECEIVED