

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-075-20289-00-00  
Spot: SWNE Sec/Twnshp/Rge: 30-24S-40W  
3226 feet from S Section Line, 1922 feet from E Section Line  
Lease Name: WOOD Well #: 4-30  
County: HAMILTON Total Vertical Depth: 2450 feet

Operator License No.: 32334  
Op Name: CHESAPEAKE OPERATING, LLC  
Address: 6100 N WESTERN AVE PO BOX 18496  
OKLAHOMA CITY, OK 73118

String	Size	Depth (ft)	Pulled (ft)	Comments
PROD	4.5	2440	0	WITH 550 SX CMT
SURF	8.625	587		WITH 400 SX CMT

Well Type: GAS UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/11/2015 9:00 AM  
Plug Co. License No.: 33961 Plug Co. Name: CONSOLIDATED OIL WELL SERVICES LLC  
Proposal Rcvd. from: DENNIS FRICK Company: CHESAPEAKE OPERATING Phone: (620) 277-0803

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 08/11/2015 1:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

PUMP 100 SX CMT WITH 200# HULLS TO 2358'. DISPLACE WITH WATER TO 1140' & PRESSURE TO 600#. HOLDING. RAN CBL. APPARENT TOC @ 586'. PERFORATE AT 574'. ATTEMPT TO PUMP INTO AT 1500 PSI. COULD NOT. REPERF AT 350'. ATTEMPT TO PUMP INTO AT 1500 PSI. COULD NOT. APPARENTLY HAVE LIGHT CONTAMINATED CMT BEHIND THE 4 1/2" CASING. RUN TBG TO 600' & CIRCULATE CMT TO SURFACE WITH 40 SX CMT. TOOH WITH TBG & TOP OFF WITH 120 SX CMT. PUMP 2 SX CMT DOWN THE ANNULUS TO 400#.

Perfs:

Top	Bot	Thru	Comments
2351	2358		

Remarks: \*\*COMPLIANCE ISSUE: DENIED TA LACK OF LEASE\*\* USED 60/40 POZMIX 4% GEL BY CONSOLIDATED.

Plugged through: TBG

SEP 02 2015  
CKM

District: 01

Signed

Ken Jehlik  
(TECHNICIAN)

RECEIVED  
AUG 24 2015  
KCC DODGE CITY

KCC WICHITA

AUG 26 2015 Form CP-2/3

RECEIVED