

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-195-22384-00-00
Spot: NE Sec/Twnshp/Rge: 22-15S-21W
1320 feet from N Section Line, 1150 feet from E Section Line
Lease Name: FIST FULL OF DOLLARS Well #: 1
County: TREGO Total Vertical Depth: 4250 feet

Operator License No.: 3532 String Size Depth (ft) Pulled (ft) Comments
Op Name: CMX, INC. PROD 5.5 4269 200 SX
Address: 1700 N WATERFRONT PKWY BLDG 300 SURF 8.625 295 175 SX
WICHITA, KS 67206

Well Type: OIL UIC Docket No: Date/Time to Plug: 07/30/2015 9:00 AM
Plug Co. License No.: 33905 Plug Co. Name: ROYAL DRILLING INC
Proposal Rcvd. from: KEITH BRIGHT Company: CMX, INC. Phone: (316) 239-8593

Proposed Plugging Method: Ordered 325 sx 60/40 pozmix 4% gel cement w/400 # hulls and 19 sx gel.
Perforations at 4012' - 4108'.
DV Tool at 1650' w/425 sx cement.

Plugging Proposal Received By: RICHARD WILLIAMS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 07/30/2015 12:45 PM KCC Agent: MARVIN MILLS

Actual Plugging Report:

Ran tubing to 3979' and pumped 19 sx gel followed by 50 sx cement w/150 # hulls. Pulled tubing to 1714' and pumped 200 sx cement. Good circulation of cement. Pulled tubing out and topped off w/35 sx cement full. Tied on to backside and squeezed w/40 sx cement. Shut in pressure 200 psi.

GPS: 38.73782 -09964257

Perfs:

Top	Bot	Thru	Comments
4012	4108		


Remarks: ALLIED CEMENT TICKET # 65586

Plugged through: TBG

SEP 02 2015
CKM

District: 04

Signed



(TECHNICIAN)

CM

AUG 03 2015

Received
KANSAS CORPORATION COMMISSION

Form CP-2/3

AUG 21 2015

CONSERVATION DIVISION
WICHITA, KS