

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-175-21901-00-00
Spot: SENWNWNE Sec/Twnshp/Rge: 26-31S-31W
4855 feet from S Section Line, 2208 feet from E Section Line
Lease Name: SAUNDERS TRUST A Well #: 1--26
County: SEWARD Total Vertical Depth: 6000 feet

Operator License No.: 30931
Op Name: DAYSTAR PETROLEUM, INC.
Address: 522 N. MAIN ST PO BOX 560
EUREKA, KS 67045

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		5400		WITH 2 SX CMT
CIBP		5910		
PROD 4.5		5997	1775	WITH 200 SX CMT
SURF 8.625		1722		WITH 1000 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 08/04/2015 8:30 AM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Revd. from: JAMI HARRIS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2943

Proposed Plugging Method: CIBP @ 5400' WITH 2 SX CMT. PLUG AT 1770' WITH 10 SX GEL & 50 SX CMT. PLUG AT 550' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: WADE KLAUS WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/11/2015 3:00 PM KCC Agent: WADE KLAUS

Actual Plugging Report:

CIBP @ 5400' WITH 2 SX CMT. 1ST PLUG AT 1770' WITH 50 SX CMT. 2ND PLUG AT 559' WITH 50 SX CMT. LOST CIRCULATION. PULLED TO 40'. NO CIRCULATION WITH WATER. LET SIT. 8/7/15: TAGGED CMT AT 396'. COULDN'T GET CIRCULATION. 8/11/15: BP @ 290' WITH RUBBER PLUG, SAND AND ROCKS. PUMPED 150 SX CMT & 250# HULLS AT 150'. CMT CIRCULATED & FELL BACK. LET SIT ONE HOUR. PUMPED 50 SX CMT & 150# HULLS AT 90'. CMT CIRCULATED TO SURFACE & HELD.

Perfs:

Top	Bot	Thru	Comments
5941	5945		
5457	5463		

KCC WICHITA

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND ACID.


AUG 26 2015

Plugged through: CSG

RECEIVED
SEP 02 2015
CKM

District: 01

Signed



(TECHNICIAN)

RECEIVED
AUG 19 2015
KCC DODGE CITY

