

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-175-21948-00-01
Spot: E2SE Sec/Twnshp/Rge: 22-31S-31W
1286 feet from S Section Line, 638 feet from E Section Line
Lease Name: LYNNA Well #: 2-22
County: SEWARD Total Vertical Depth: 5990 feet

Operator License No.: 30931
Op Name: DAYSTAR PETROLEUM, INC.
Address: 522 N. MAIN ST PO BOX 560
EUREKA, KS 67045

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		5030		WITH 2 SX CMT
PROD	5.5	5980	2430	WITH 175 SX CMT
SURF	8.625	1729		WITH 800 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 08/13/2015 2:00 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: JAMI HARRIS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2943

Proposed Plugging Method: CIBP @ 5036' WITH 2 SX CMT. PLUG AT 1780' WITH 10 SX GEL & 50 SX CMT. PLUG AT 550' WITH 50 SX CMT. PLUG AT 40' WITH 20 SX CMT.

Plugging Proposal Received By: WADE KLAUS Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/13/2015 5:00 PM KCC Agent: WADE KLAUS

Actual Plugging Report:

CIBP @ 5030' WITH 2 SX CMT. 1ST PLUG AT 1781' WITH 10 SX GEL & 50 SX CMT.
2ND PLUG AT 540' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 20 SX CMT.

Perfs:

Top	Bot	Thru	Comments
5474	5478		
5460	5462		
5454	5458		

Remarks: USED 60/40 POZMIX 4% GEL BY COPELAND.

Plugged through: CSG

KCC WICHITA
AUG 26 2015
RECEIVED

District: 01

Signed [Signature]

(TECHNICIAN)

SEP 02 2015
CKM

RECEIVED
AUG 19 2015
KCC DODGE CITY