

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-185-23764-00-00
Spot: W2NENWSW Sec/Twnshp/Rge: 29-23S-13W
2285 feet from S Section Line, 745 feet from W Section Line
Lease Name: FAIRCHILD Well #: 1
County: STAFFORD Total Vertical Depth: 3983 feet

Operator License No.: 34730
Op Name: DEMCO OIL AND GAS COMPANY
Address: 1335 S. 6TH ST
BLACKWELL, OK 74631

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3820		
PROD	5.5	3913	0	WITH 140 SX CMT
SURF	8.625	221		WITH 165 SX CMT

Well Type: OIL UIC Docket No: _____ Date/Time to Plug: 08/17/2015 2:00 PM
Plug Co. License No.: 31529 Plug Co. Name: MIKE'S TESTING & SALVAGE, INC.
Proposal Rcvd. from: JAMI HARRIS Company: MIKE'S TESTING & SALVAGE, INC Phone: (620) 938-2943

Proposed Plugging Method: SAND BACK PERFS TO 3610' WITH 5 SX CMT. PERFORATE AT 800' & CIRCULATE CMT TO SURFACE BOTH INSIDE & OUT.

Plugging Proposal Received By: ERIC MACLAREN WitnessType: COMPLETE (100%)
Date/Time Plugging Completed: 08/17/2015 4:05 PM KCC Agent: ROBERT DICKERSON

Actual Plugging Report:

SAND BACK PERFS TO 3610' WITH 5 SX CMT. PERFORATE AT 800' THROUGH TBG & CIRCULATE CMT TO SURFACE. DID CIRCULATE BOTH INSIDE & OUT OF ANNULUS. PULL TBG & TIED ONTO BACKSIDE. PRESSURED TO 500 PSI. USED 250 SX COMMON CMT WITH 10 SX 3% CC. TOP OFF WITH 10 SX CMT.

Perfs:

Top	Bot	Thru	Comments
3866	3872		
3799	3803		
3664	3676		

Remarks: **COMPLIANCE ISSUE: DENIED TA NEED CURRENT FL** USED COMMON CMT BY COPELAND ACID.

Plugged through: TBG

District: 01

Signed Robert Dickerson SEP 02 2015 CKM

(TECHNICIAN)

RECEIVED
AUG 19 2015
KCC DODGE CITY

KCC WICHITA

AUG 26 2015

RECEIVED