

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-015-19740-00-00  
Spot: SESE Sec/Twnshp/Rge: 35-24S-3E  
660 feet from S Section Line, 660 feet from E Section Line  
Lease Name: MULNIX Well #: 1  
County: BUTLER Total Vertical Depth: 2723 feet

Operator License No.: 33974  
Op Name: EAGLE CREEK RESOURCES, LLC  
Address: PO BOX 377  
SEWICKLEY, PA 15143

| String | Size | Depth (ft) | Pulled (ft) | Comments |
|--------|------|------------|-------------|----------|
| COND   | 15.5 | 68         |             |          |
| PROD   | 6    | 2714       |             | 100 SX   |
| SURF   | 15.5 | 68         |             | 100 SX   |
| SURF   | 12.5 | 1135       |             |          |

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/17/2015 8:00 AM  
Plug Co. License No.: 5870 Plug Co. Name: PHILLIPS WELL SERVICE, INC.  
Proposal Rcvd. from: GREG EILERT Company: EAGLE CREEK RESOURCES Phone: (316) 214-3456

Proposed Plugging Method: AS ACCORDING TO THE KCC RULES & REGULATIONS

Plugging Proposal Received By: JEFF KLOCK Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 07/21/2015 3:00 PM KCC Agent: JONATHAN HILL

Actual Plugging Report:

7/17/2015: RAN IN HOLE W/NOTCHED COLLAR ON TUBING. BRIDGE AT SURFACE FROM 8' TO 10', RAN DOWN TO 1000' HIT NEW BRIDGE. TURNED ON BRIDGE FROM APPROX. 3 HOURS. - PULLED TUBING AND RAN IN W/IMPRESSSION BLOCK. FOUND UNKNOWN SQUARE OBJECT AS BRIDGE. 7/20/2015: RAN IN W/FLAT BOTTOM MILL. BROKE THROUGH BRIDGE AND MADE IT DOWN TO 2120'. DID NOT MAKE ANYMORE PROGRESS DOWN-HOLE. DECISION MADE TO PLUG AT THIS POINT. 7/22/2015: - 1) DUG OUT OLD CELLAR, FOUND TOP OF 12.5" CASING. DID NOT LOCATE 15.5" CASING. 2) TRIPPED IN TUBING DOWN TO 2120', FOUND BRIDGE. PUMPED 50 SKS OF CLASS A CEMENT W/3% CACL AND 0.25 LB/SK CELLOFLAKE. 3) PULL TUBING UP, TAGGED CEMENT AT 2007'. 4) DYNALOG PERFORATED CASING AT 257' W/4 SHOTS. 5) TIED INTO CASING AND PUMPED 230 SKS CLASS A. CIRCULATED CEMENT UP ALL CASINGS TO SURFACE.

Perfs:

| Top  | Bot  | Thru | Comments |
|------|------|------|----------|
| 2680 | 2720 | OH   |          |

Remarks: CEMENTING COMPELTED BY CONSOLDIATED OIL WELL SERVICES, LLC, ELDORADO, KS. TICKET #46182. PLUGGED DUE TO COMPLIANCE WITH KAR 82-3-111.

Plugged through: TBG

SEP 02 2015  
CKM

District: 02

Received  
KANSAS CORPORATION COMMISSION Signed

Jonathan Hill

AUG 21 2015

(TECHNICIAN)

CONSERVATION DIVISION  
WICHITA, KS

Form CP-2/3

14