

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-165-20741-00-00  
Spot: SESWNE Sec/Twnshp/Rge: 1-16S-20W  
3035 feet from S Section Line, 1635 feet from E Section Line  
Lease Name: WATSON Well #: 1  
County: RUSH Total Vertical Depth: 3695 feet

Operator License No.: 5042  
Op Name: EDMISTON OIL COMPANY, INC.  
Address: 125 N MARKET STE 1130  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3350		WITH 2 SX CMT
PROD	4.5	3691	0	WITH 150 SX CMT
SURF	8.625	1330		WITH 250 SX CMT

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 07/29/2015 10:00 AM  
Plug Co. License No.: 6426 Plug Co. Name: EXPRESS WELL SERVICE & SUPPLY INC  
Proposal Rcvd. from: SHANNON RAYBERN Company: EDMISTON OIL Phone: (620) 793-6924

Proposed Plugging Method: SET CIBP 50' ABOVE PERFS. TEST CASING. IF HOLDS PRESSURE PERFORATE AT 1380'. RUN TBG TO 1300' & CIRCULATE CMT TO SURFACE.

Plugging Proposal Received By: SCOTT ALBERG Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 07/29/2015 2:30 PM KCC Agent: MICHAEL MAIER

Actual Plugging Report:

SET CIBP @ 3350' WITH 2 SX CMT. TEST CASING. HELD AT 500#. PERFORATED AT 1380'. RUN TBG TO 1300' & PUMPED 350 SX CMT. CMR CIRCULATED TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
3691	3695		
3502	3505		
3408	3412		

Remarks: \*\*COMPLIANCE ISSUE: DENIED TA NEED FL\*\* USED 60/40 POZMIX 4% GEL BY CONSOLIDATED.

Plugged through: TBG

SEP 02 2015  
CKM

District: 01

Signed

*Michael Maier*  
5A

(TECHNICIAN)

Received  
KANSAS CORPORATION COMMISSION

AUG 21 2015

CONSERVATION DIVISION  
WICHITA, KS

RECEIVED  
AUG 18 2015  
KCC DODGE CITY

Form CP-2/3