

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-015-19477-00-00  
Spot: N2SWSW Sec/Twnshp/Rge: 7-26S-5E  
990 feet from S Section Line, 4620 feet from E Section Line  
Lease Name: HIGGINS Well #: 2  
County: BUTLER Total Vertical Depth: 2390 feet

Operator License No.: 5446  
Op Name: GILES, BENJAMIN M.  
Address: 346 S. LULU  
WICHITA, KS 67211

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		1770		
PROD	5.5	2390		Parted at unknown depth
SURF	8.625	200		100 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/17/2015 8:00 AM  
Plug Co. License No.: 5446 Plug Co. Name: GILES, BENJAMIN M.  
Proposal Rcvd. from: DUSTY GREEN Company: GILES, BENJAMIN M. Phone: (316) 265-1992

Proposed Plugging Method: TO BE PLUGGED IN ACCORDANCE WITH THE RULES AND REGULATIONS OF THE KANSAS CORPORATION COMMISSION.

Plugging Proposal Received By: JEFF KLOCK WitnessType: COMPLETE (100%)  
Date/Time Plugging Completed: 08/25/2015 11:00 AM KCC Agent: JONATHAN HILL

Actual Plugging Report:

SEVERAL ATTEMPTS MADE TO REACH BOTTOM OF WELL BETWEEN 7/22/2015 TO 8/4/2015. PARTED CASING AT 295' (CONFIRMED W/IMPRESSION BLOCK), WAS ABLE TO WORK TUBING STRING BELOW DOWN TO 400' WHERE NO FURTHER PROGRESS WAS MADE WITH NOTCHED COLLAR/BIT/MILL. CCL RAN IN HOLE INDICATED USING CASING PARTED AT 279' AND WAS UNABLE TO LOCATE ANY COLLARS BELOW 193'. 5.5" CASING SHOT AT 160' IN ORDER TO PULL, BUT COULD STILL NOT FREE FROM HOLE. -- PLUGGING: 1) TUBING RAN IN TO 250', PUMPED 75 SKS OF CLASS A (NO BLEND) CEMENT W/4% CACL AND 4 SKS HULLS. FULL CIRCULATION INITIALLY, THEN ANNULAR DROPPED OFF WHILE CIRCULATION UP 5.5" CONTINUED. 2) PULLED TUBING OUT OF HOLE AND TIED INTO 5.5" CASING. PUMPED ADDITIONAL 70 SKS CEMENT AND CIRCULATED CEMENT UP BACKSIDE TO SURFACE. 3) WAITED APPROX. 1 HOUR TO OBSERVE CEMENT REMAINED AT SURFACE.

Perfs:

Remarks: CEMENTING COMPLETED BY GRESSEL OILFIELD SERVICE, HAYSVILLE, KS. TICKET #43109. PLUGGED DUE TO COMPLIANCE ISSUE WITH 82-3-111.

Plugged through: TBG

SEP 02 2015  
CKM

District: 02

Signed

Jonathan Hill

(TECHNICIAN)  
KCC WICHITA

AUG 28 2015

Form CP-2/3

RECEIVED

IX