

TO:  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
266 N. Main St., Ste. 220  
Wichita, KS 67202-1513

API Well Number: 15-051-24744-00-00  
Spot: S2N2SE Sec/Twnshp/Rge: 17-14S-20W  
1613 feet from S Section Line, 1450 feet from E Section Line  
Lease Name: KINGSLEY A Well #: 3  
County: ELLIS Total Vertical Depth: 3818 feet

Operator License No.: 5552  
Op Name: GORE OIL COMPANY  
Address: 202 S ST FRANCIS PO BOX 2757  
WICHITA, KS 67202

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		3670		
PROD	4.5	3802		150 SX
SURF	8.625	207		135 SX

Well Type: OIL UIC Docket No: \_\_\_\_\_ Date/Time to Plug: 08/25/2015 8:30 AM  
Plug Co. License No.: 34082 Plug Co. Name: ALLIANCE WELL SERVICE INC.  
Proposal Rcvd. from: LENNY DINKEL Company: GORE OIL CO Phone: (785) 623-0123

Proposed Plugging Method: Ordered 450 sx 60/40 pozmix 4% gel cement, 600 # hulls.  
AC-O1-PC Alt II 1420' w/400 sx cement.  
Squeezed 509' - 632'  
Casing leaks - 2837' - 2871'; 2070' - 2132'; 2628' - 2652'  
Perforations: 3609' - 3615', 3633' - 3644', 3764' - 3766', 3778' - 3780', 3452' - 3517'  
Bridge plug - 3670'

Plugging Proposal Received By: RICHARD WILLIAMS Witness Type: COMPLETE (100%)  
Date/Time Plugging Completed: 08/25/2015 12:30 PM KCC Agent: PAT STAAB

Actual Plugging Report:

Red line ran in hole with tubing to 2970' and pumped 125 sx cement w/200 # hulls. Pulled tubing to 2340'. Allied rigged to tubing and pumped 125 sx cement w/200 # hulls. Pulled tubing to 1395'. Allied rigged to tubing and pumped 40 sx cement w/50 # hulls to circulate cement to pit area. Pulled tubing. Rigged to 4 1/2" casing with a swedge and pumped 20 sx cement w/300 psi. Shut in pressure 300 psi. Rigged to 8 5/8" surface pipe and pumped 10 sx cement w/200 psi. Shut in pressure 200 psi.

GPS: 38.83161 -099.56404

Perfs:

Top	Bot	Thru	Comments
3778	3780		
3764	3766		
3633	3644		
3609	3615		

Received  
KANSAS CORPORATION COMMISSION  
**AUG 31 2015**  
CONSERVATION DIVISION  
WICHITA, KS


Remarks: ALLIED CEMENTING CO TICKET # 055800

Plugged through: TBG

SEP 02 2015  
CM

District: 04

Signed

  
(TECHNICIAN)

CM

AUG 25 2015