

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-055-21404-00-01
Spot: NWSESE Sec/Twnshp/Rge: 34-23S-34W
1010 feet from S Section Line, 1000 feet from E Section Line
Lease Name: GARDEN CITY COMPANY A Well #: 6-34
County: FINNEY Total Vertical Depth: 1522 feet

Operator License No.: 30535
Op Name: HARTMAN OIL CO., INC.
Address: 10500 E BERKELEY SQ PKWY STE 100
WICHITA, KS 67206

String	Size	Depth (ft)	Pulled (ft)	Comments
CIBP		1522		
SURF	8.625	1634		WITH 525 SX CMT

Well Type: SWD UIC Docket No: D27186.0 Date/Time to Plug: 08/10/2015 10:00 AM
Plug Co. License No.: 99996 Plug Co. Name: ALLIED CEMENT COMPANY
Proposal Rcvd. from: STAN MITCHELL Company: HARTMAN OIL Phone: (620) 272-1025

Proposed Plugging Method: PLUGGING PROPOSAL SAME AS ACTUAL PLUGGING.

Plugging Proposal Received By: KEN JEHLIK Witness Type: COMPLETE (100%)
Date/Time Plugging Completed: 08/10/2015 2:30 PM KCC Agent: KEN JEHLIK

Actual Plugging Report:

CIBP @ 1522'. SAND FILL UP AT 1350'. RUN TBG TO 1348' & SPOT 30 SX CMT.
PULL TBG TO 986' & SPOT 30 SX CMT. PULL TBG TO 604' & CIRCULATE CMT TO
SURFACE WITH 153 SX CMT. TOOH & TOP OFF WITH 12 SX CMT.

Perfs:

Top	Bot	Thru	Comments
1442	1502		

Remarks: **COMPLIANCE ISSUE: FAILED MIT** USED 60/40 POZMIX 4% GEL BY ALLIED.

Plugged through: TBG

SEP 02 2015
CKM

District: 01

Signed

Ken Jehlik
5A

(TECHNICIAN)

RECEIVED
AUG 19 2015
KCC DODGE CITY
MR

KCC WICHITA

Form CP-2/3

AUG 26 2015

RECEIVED

UIC