

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-119-21344-00-00
Spot: SENWSWNW Sec/Twnshp/Rge: 26-33S-26W
1685 feet from N Section Line, 345 feet from W Section Line
Lease Name: COOLHAND Well #: 1-26
County: MEADE Total Vertical Depth: 7500 feet

Operator License No.: 3273
Op Name: HERMAN L. LOEB, LLC
Address: PO BOX 838
LAWRENCEVILLE, IL 62439

String	Size	Depth (ft)	Pulled (ft)	Comments
PC	5.5	2609		WITH 320 SX CMT
PROD	5.5	7388	1681	WITH 300 SX CMT
SURF	8.625	1403		WITH 480 SX CMT

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 08/03/2015 10:30 AM
Plug Co. License No.: 32833 Plug Co. Name: SARGENT LILLARD CASING PULLING, INC.
Proposal Rcvd. from: KIRBY LILLARD Company: SARGENT LILLARD CASING PULL Phone: (580) 254-1881

Proposed Plugging Method: SET CIBP 50' ABOVE PERFS WITH 2 SX CMT OR 25 SX CMT WITH 200# HULLS. PLUG AT 1450' WITH 50 SX CMT. PLUG AT 200' WITH 50 SX CMT.

Plugging Proposal Received By: MICHAEL MAIER Witness Type: PARTIAL
Date/Time Plugging Completed: 08/03/2015 4:30 PM KCC Agent: LARRY HARRIS

Actual Plugging Report:

PUMP 25 SX CMT & 200# HULLS AT 6310'. 1ST PLUG AT 1430' WITH 50 SX CMT.
2ND PLUG AT 200' WITH 60 SX CMT TO SURFACE.

Perfs:

Top	Bot	Thru	Comments
6360	6377		

Received
KANSAS CORPORATION COMMISSION
AUG 20 2015
CONSERVATION DIVISION
WICHITA, KS

Remarks: USED CLASS A CEMENT BY SARGENT LILLARD.

Plugged through: CSG

SEP 02 2015
CKM

District: 01

Signed

Larry A. Harris P.F.R.T. - *et*
(TECHNICIAN)
5A

RECEIVED
AUG - 7 2015
KCC DODGE CITY