

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
266 N. Main St., Ste. 220
Wichita, KS 67202-1513

API Well Number: 15-051-26797-00-00
Spot: SWNENENW Sec/Twnshp/Rge: 16-11S-16W
355 feet from N Section Line, 2271 feet from W Section Line
Lease Name: CRAIG Well #: 1
County: ELLIS Total Vertical Depth: 3420 feet

Operator License No.: 5663
Op Name: HESS OIL COMPANY
Address: PO BOX 1009
MCPHERSON, KS 67460

<u>String</u>	<u>Size</u>	<u>Depth (ft)</u>	<u>Pulled (ft)</u>	<u>Comments</u>
<u>SURF</u>	<u>8.625</u>	<u>218</u>		<u>150 sx</u>

Well Type: DH UIC Docket No: _____ Date/Time to Plug: 08/22/2015 12:00 AM
Plug Co. License No.: 4958 Plug Co. Name: MALLARD, J. V., INC.
Proposal Rcvd. from: KATHY Company: MALLARD, J. V., INC. Phone: (620) 241-4630

Proposed Plugging Method: Ordered 285 sx 60/40 pozmix - 4% gel cement with 1/4# flo- seal per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received By: CASE MORRIS Witness Type: NONE
Date/Time Plugging Completed: 08/22/2015 2:30 PM KCC Agent: CASE MORRIS

Actual Plugging Report:

1st plug @3354 w/50 sx
2nd plug @1000 w/50 sx
3rd plug @500 w/80 sx
4th plug @250 w/50 sx
5th plug @40 w/10 sx

Rathole 30 sx Mousehole 15 sx

Perfs:

Received
KANSAS CORPORATION COMMISSION
AUG 31 2015
CONSERVATION DIVISION
WICHITA, KS

Remarks: QUALITY

Plugged through: DP

SEP 02 2015
CKM

District: 04

Signed Craig Morris
(TECHNICIAN)

AUG 25 2015