


B

STATE OF KANSAS  
STATE CORPORATION COMMISSION

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above Section Plat

Kiowa County, Sec. 28 Twp. 27S Rge. 20 (X) (W) (XX)  
Location as "NE/CNW/SW" or footage from lines Gen NW/4 SW/4  
Lease Owner Roland S. Bond  
Lease Name Zeigler Well No. 1  
Office Address 2600 Republic National Bank Bldg. Dallas, Texas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole  
Date well completed Jan 31 19 60  
Application for plugging filed Jan 31 19 60  
Application for plugging approved Jan 31 19 60  
Plugging commenced Jan 31 19 60  
Plugging completed Jan 31 19 60  
Reason for abandonment of well or producing formation Dry hole

If a producing well is abandoned, date of last production None 19       
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Bill Lee Kamp Stafford, Kansas  
Producing formation None Depth to top      Bottom      Total Depth of Well 5010 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Heebner Shale		4115	4120	9 5/8"	415'	None
Toronto Limestone		4132	4166			
Douglas Formation		4166	4258			
Lansing-Kansas City Limestone		4268	4624			
Marmaton Limestone		4678	4836			
Mississippi	Water-Show	4878	5010			
	Oil & Gas					

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from      feet to      feet for each plug set.

Filled hole with mud up to 400 feet. Put Halliburton plug at 400 feet with 3 gallon of hulls on top of plug and placed 25 sacks of cement on top of hulls through drill pipe. Filled with mud up to 35 feet. Put Halliburton plug at 35 feet with 3 gallons of hulls on top of plug and 10 sacks of cement on top of hulls.

RECEIVED  
STATE CORPORATION COMMISSION  
MAR 7 1960  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Garvey Drilling Co.  
Address Wichita, Kansas

STATE OF Oklahoma, COUNTY OF Key, ss.  
Melvin F. Endicott - Agent (~~employee~~ of owner) (~~owner~~ or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Melvin F. Endicott

(Address)     

SUBSCRIBED AND SWORN TO before me this 23 day of February, 1960  
Dorcas Bern Alston

My commission expires 12-1-63

Notary Public.



# WELL LOG

COMPANY ROLAND S. BOND

SEC. 28 T. 27S. R. 20W

FARM ZIEGLER

NO. 1

LOC. C-NW, SW


TOTAL DEPTH 5010'

COUNTY KIOWA CO., KANSAS

COMM. January 16, 1960

COMP. January 31, 1960

CONTRACTOR GARVEY DRILLING COMPANY



CASING 9 5/8" @ 415' w/350 sax.

ELEVATION

PRODUCTION D & A

FIGURES INDICATE BOTTOM OF FORMATIONS

65	Surface soil, sand & grav el
90	Blue shale
130	Sand
670	Shale
750	Red bed & shale
775	Anhydrite
1310	Shale
2420	Shale w/lime streaks
2652	Lime
2730	Lime & shale
2948	Lime
2960	Lime & shale
3077	Shale w/lime streaks
3785	Lime & shale
3940	Shale & chalky lime
4021	Chalky lime
4090	Chalky lime & shale
4210	Lime & shale
4266	Shale & lime
4818	Lime
4851	Lime & shale
4940	Lime
5010	Lime & shale
5010	T. D.

RECEIVED  
STATE CORPORATION COMMISSION

MAY 20 1963

CONSERVATION DIVISION  
Wichita, Kansas

State of KANSAS  
County of BARTON } ss:

I, VERNE A. MORRIS of GARVEY DRILLING COMPANY

upon oath state that the above and foregoing is a true and correct copy of the log of the #1 ZIEGLER well.

Subscribed and sworn to before me this 9th day of February 19 60

My Commission Expires: November 12, 1962

*Verne A. Morris*  
*[Signature]*  
NOTARY PUBLIC