

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Kiowa County, Sec. 28 Twp. 27S Rge. 20W (B) ~~XXXXXX~~

Location as "NE/CNW/SW" or footage from lines C NW SE

Lease Owner Mull Drilling Company, Inc.

Lease Name Zeigler Well No. 4

Office Address 1625 Wichita Plaza Building, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 9-11-65 19

Application for plugging filed 9-11-65 19

Application for plugging approved 9-11-65 19

Plugging commenced 9-11-65 19

Plugging completed 9-11-65 19

Reason for abandonment of well or producing formation commercial quantities of oil not found

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Archie Elving

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4898 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	544'	

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Set bottom plug @ 300' w/ 25 sx. cement thru DP
Set top plug @ 40' w/ 10 sx. cement
2 sx. cement in rathole

RECEIVED
STATE CORPORATION COMMISSION
RECEIVED
STATE CORPORATION COMMISSION
SEP 20 1965
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Walters Drilling Co.
Address 510 Orpheum Building, Wichita, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.
Robert F. Walters (employee of owner) or (owner of property)

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Robert F. Walters

510 Orpheum Building, Wichita, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 17th day of September 19 65

My commission expires October 4, 1967

Juanita M. Green Notary Public.



DRILLER'S LOG

COMPANY: MULL DRILLING COMPANY, INC.
1625 WICHITA PLAZA BUILDING
WICHITA, KANSAS

WELL NAME: ZEIGLER #4
C NW SE SEC. 28-27S-20W
KIOWA COUNTY, KANSAS

CONTRACTOR: WALTERS DRILLING CO.
510 ORPHEUM BUILDING
WICHITA, KANSAS

ROTARY DRILLING COMMENCED: AUGUST 29, 1965
ROTARY DRILLING COMPLETED: SEPTEMBER 11, 1965

ELEVATION: 2303 KB

CASING RECORD: 8 5/8" @ 544' w/ 275 sacks cement

LOG

0 - 90	Sand
90 - 460	Shale and Shells
460 - 540	Shale
540 - 550	Sand
550 - 820	Red Bed
820 - 1280	Shale
1280 - 1300	Anhydrite
1300 - 1430	Shale and Shells
1430 - 1840	Shale
1840 - 2285	Shale and Shells
2285 - 2470	Shale and Lime
2470 - 2555	Lime and Shale
2555 - 2765	Lime
2765 - 3210	Lime and Shale
3210 - 4040	Shale and Lime
4040 - 4215	Lime and Shale
4215 - 4320	Shale and Lime
4320 - 4735	Lime
4735 - 4804	Lime and Shale
4804 - 4868	Lime and Shale
4868 - 4870	Lime
4868 - 4873	Core (2' Corr.)
4873 - 4887	Core #1
4887 - 4898	Core #2
<u>4898</u>	<u>Rotary Total Depth - D & A</u>


RECEIVED
STATE CORPORATION COMMISSION

SEP 20 1965


CONSERVATION DIVISION
Wichita, Kansas

The undersigned, Robert F. Walters, hereby certifies, in behalf of said company that the above log is a true and correct log of the formations encountered in drilling the above well as reflected by the Daily Drilling Reports.

WALTERS DRILLING CO.

BY 
ROBERT F. WALTERS, Partner

Subscribed and sworn to before me this 17th day of September, 1965.


Juanita M. Green, Notary Public

My Commission Expires: October 4, 1967