

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

WELL PLUGGING RECORD

Kiowa County, Sec. 29 Twp. 27S Rge. 20W (E) (W)

Location as "NE/CNW/SW" or footage from lines NW NE Sec. 29-27S-20W

Lease Owner Mull Drilling Co. & Walters Drilling Co. et al

Lease Name Breising 'D' Well No. 1

Office Address 1625 Wichita Plaza Building, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 3-19-66

Application for plugging filed 3-19-66

Application for plugging approved 3-19-66

Plugging commenced 3-19-66

Plugging completed 3-19-66

Reason for abandonment of well or producing formation commercial quantities of oil not found

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Archie Elving - Pratt, Kansas

Producing formation Depth to top Bottom Total Depth of Well 4980 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	560'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plug and 25 sacks cement at 300'

Plug and 10 sacks cement at 40'

2 sacks cement - rathole

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Walters Drilling Co.
Address 510 Orpheum Building, Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEDGWICK ss.
Robert F. Walters (owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.



(Signature) Robert F. Walters

510 Orpheum Building, Wichita, Kansas
(Address)

Subscribed and sworn to before me this 29th day of March 19 66

My commission expires October 4, 1967

Juanita M. Green
Notary Public.



DRILLER'S LOG

COMPANY: MULL DRILLING CO., & WALTERS DRILLING CO. etal
 1625 Wichita Plaza Building
 Wichita, Kansas

WELL NAME: BRENSING 'D' #1
 NW NE Section 29-27S-20W
 Kiowa County, Kansas

CONTRACTOR: WALTERS DRILLING CO.
 510 Orpheum Building
 Wichita, Kansas

ROTARY DRILLING COMMENCED: MARCH 4, 1966
 ROTARY DRILLING COMPLETED: MARCH 19, 1966

ELEVATION: 2318 KB

SURFACE CASING RECORD: 8 5/8" set at 560' w/ 290 sacks cement

RECEIVED
 STATE CORPORATION COMMISSION
 MAR 31 1966
 CONSERVATION DIVISION
 Wichita, Kansas

LOG

0 - 98	Sand
98 - 430	Shale and Shells
430 - 560	Shale
560 - 830	Shale and Red Bed
830 - 1309	Shale
1309 - 1332	Anhydrite
1332 - 1470	Shale
1470 - 1985	Shale and Shells
1985 - 2380	Shale and Lime Streaks
2380 - 2509	Lime and Shale
2509 - 2760	Lime
2760 - 2905	Shale and Lime
2905 - 3210	Lime and Shale
3210 - 3435	Shale and Lime
3435 - 3545	Lime and Shale
3545 - 3555	Shale
3555 - 3620	Shale and Lime
3620 - 3765	Lime and Shale
3765 - 4000	Shale and Lime
4000 - 4390	Lime and Shale
4390 - 4886	Lime
4886 - 4908	Core
4908 - 4980	Lime
<u>4980</u>	<u>Rotary Total Depth - D & A</u>

The undersigned, Robert F. Walters, hereby certifies, in behalf of said company that the above log is a true and correct log of the formations encountered in drilling the above well as reflected by the Daily Drilling Reports.

WALTERS DRILLING CO.

BY



 ROBERT F. WALTERS, Partner

Subscribed and sworn to before me
 this 29th day of March, 1966.



 Juanita M. Green, Notary Public

My Commission Expires: October 4, 1967