

STATE OF KANSAS
 STATE CORPORATION COMMISSION
 200 Colorado Derby Building
 Wichita, Kansas 67202

WELL PLUGGING RECORD
 K.A.R.-82-3-117

15-097-30014-0000

TYPE OR PRINT
 NOTICE: Fill out completely
 and return to Cons. Div.
 office within 30 days.

API NUMBER _____
 LEASE NAME Bissitt
 WELL NUMBER A-1
 _____ Ft. from S Section Line
 _____ Ft. from E Section Line
 C SE NE
 SEC. 29 TWP. 27S RGE. 20W (E) or (W)
 COUNTY Kiowa
 Date Well Completed _____
 Plugging Commenced 9-30-87
 Plugging Completed 10-12-87

LEASE OPERATOR Mull Drilling Company, Inc.
 ADDRESS P.O. Box 2758
Wichita, Kansas 67201
 PHONE # (316) 264-6366 OPERATORS LICENSE NO. 5144

Character of Well Oil
 (Oil, Gas, D&A, SWD, Input, Water Supply Well)
 Did you notify the KCC District Office prior to plugging this well? Yes
 Which KCC Office did you notify? Dist. #1 Dodge City, Kansas
 Is ACO-1 filed? _____ If not, is well log attached? _____

Producing Formation _____ Depth to Top _____ Bottom _____ T.D. 4917'
 Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
				8-5/8"	550'	none
				4-1/2"	4914'	797'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.
Plugged off bottom with sand to 4840' and 4 sacks cement. Shot pipe @3519', 3009'
2511', 2018', 1703', 1510', 1312', 1215', 1116', 921', 797', pulled 25 jts. 4-1/2".
Pumped 3 hulls & 15 gel, circulated out, hole in surface. Ran 2" tubing to 780', pumped 50 sacks cement, pulled to 570', pumped 50 sacks, pulled to 30', pumped 10 sacks to top.
 (if additional description is necessary, use BACK of this form.) 60/40 pos, 6% gel. Plugging Complete.

Name of Plugging Contractor Kelso Casing Pulling, Inc. License No. 6050

Address P.O. Box 347 Chase, Kansas 67524

STATE OF Kansas COUNTY OF Rice, ss.

Mike Kelso, Vice-President (Employee of Operator) or (Operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) Mike Kelso
 (Address) Box 347 Chase, Kansas 67524

SUBSCRIBED AND SWORN TO before me this 13th day of October, 19 87

[Signature] RECEIVED
 Notary Public

My Commission Expires: _____



OCT 14 1987
 10-14-87
 CONSERVATION DIVISION
 Wichita, Kansas
 Form CP-4
 Revised 07-86