


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

Kiowa County, Sec. 23 Twp. 27S Rge. 10 (E) W(W)

Location as "NE/CNW\*SW\*" or footage from lines NW/4 NE/4  
Lease Owner Beardmore Drilling Company  
Lease Name Bowers Well No. 2  
Office Address 827 Beacon Bldg., Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) dry hole  
Date well completed 5-16 19 62  
Application for plugging filed 5-16 19 62  
Application for plugging approved 5-16 19 62  
Plugging commenced 5-16 19 62  
Plugging completed 5-16 19 62  
Reason for abandonment of well or producing formation dry hole

NORTH



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Fred Hampel  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4940 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Sand		0	175'			
Clay and shale		175'	340'	8 5/8"	340'	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

0 to 40' - 10 sacks cement

40' - wood plug

40' to 240' - heavy mud

240' to 300' - 20 sacks cement

300' - wood plug

300' to 4940' - heavy mud

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 22 1962  
5-22-62  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Gabbert-Jones Drilling Co.  
Address 514 Orpheum Bldg., Wichita, Kansas

STATE OF KANSAS COUNTY OF SEDGWICK, ss.  
Heber Beardmore (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *Heber Beardmore*  
827 Beacon Bldg., Wichita 2, Kansas

SUBSCRIBED AND SWORN to before me this 21st day of May, 1962

My commission expires 7-13-63  
Shirley Ann Jackson Notary Public.

INVOICED  
DATE 5/22/62  
INV. NO. 5040-W

GABBERT-JONES DRILLING CO., INC.  
WICHITA, KANSAS  
DRILLERS WELL LOG

BOWERS #2  
 C NW NE SECTION 23-27S-20W  
 KIOWA COUNTY, KANSAS

COMMENCED: MAY 1, 1962  
 COMPLETED: MAY 16, 1962

OPERATOR - BEARDMORE DRILLING COMPANY

DEPTH		FORMATION	REMARKS
FROM	TO		
0-	175	SAND	RAN 341' OF 8 5/8" CASING, SET @ 340' w/250 SACKS CEMENT
175	340	CLAY & SHALE	
340	550	SHALE	
550	640	SHALE & SAND	
640	685	RED BED	
685	720	LIME	
720	1270	RED BED & SHALE	
1270	1310	ANHYDRITE	
1310	1450	SHALE	
1450	2280	SHALE & SHELLS	
2280	2350	LIME & SHALE	
2350	2620	LIME	
2620	2720	LIME & SHALE	
2720	2920	LIME	
2920	4221	SHALE & LIME	
4221	4285	LIME	
4285	4381	LIME & CHERT	
4381	4620	LIME	
4620	4849	LIME & SHALE	
4849	4863	LIME	
4863	4883	LIME, CHERT & SHALE	
4883	4940	CHERT	
4940	TD		DRY & ABANDONED

**RECEIVED**  
 STATE CONSERVATION COMMISSION  
 MAY 22 1962  
 CONSERVATION DIVISION  
 Wichita, Kansas

I, J.W. GABBERT, CERTIFY THIS IS A TRUE AND CORRECT COPY OF THE DRILLER'S LOG FOR THE WELL DRILLED IN C NW NE SECTION 23-27S-20W, KIOWA COUNTY, KANSAS TO THE BEST OF MY KNOWLEDGE AND BELIEF.

STATE OF KANSAS )  
 ) SS  
 COUNTY OF SEDGWICK )

*J.W. Gabbert*  
 J.W. GABBERT

BEFORE ME, THE UNDERSIGNED, A NOTARY PUBLIC WITHIN AND FOR SAID COUNTY AND STATE, ON THIS 18TH DAY OF MAY, 1962, PERSONALLY APPEARED J.W. GABBERT TO ME PERSONALLY KNOWN TO BE THE IDENTICAL PERSON WHO EXECUTED THE WITHIN AND FOREGOING INSTRUMENT AND ACKNOWLEDGED TO ME THAT HE EXECUTED THE SAME AS HIS FREE AND VOLUNTARY ACT AND DEED FOR THE USES AND PURPOSES THEREIN SET FORTH.

IN WITNESS THEREOF, I HAVE HEREUNTO SET MY HAND AND OFFICIAL SEAL THE DAY AND YEAR LAST ABOVE WRITTEN.

MY COMMISSION EXPIRES NOVEMBER 19, 1962

*Emmet E. Hall*  
 EMMET E. HALL, NOTARY PUBLIC