


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
212 No. Market
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Kiowa County, Sec. 23 Twp. 27S Rge. (E) 20 (W)

Location as "NE/CNW/SE/SW" or footage from lines C NW NW

Lease Owner Rains & Williamson Oil Co.

Lease Name Bowers Well No. #1

Office Address 1425 Wichita Plaza Bldg., Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 6-22 19 66

Application for plugging filed 6-22 19 66

Application for plugging approved 6-22 19 66

Plugging commenced 6-22 19 66

Plugging completed 6-22 19 66

Reason for abandonment of well or producing formation no oil or gas found in commercial quantities.

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well Archie Elving, Pratt, Kansas

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4890 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|-----------|---------|------|----|--------|---------|------------|
| | | | | 8-5/8" | 556.82' | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |
| | | | | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

"Set plug at 600', cement through drill pipe with 35 sacks. Mud back to 45' and set plug. Cement through drill pipe and spot with 15 sacks. Plugged by hand.

RECEIVED
STATE CORPORATION COMMISSION
JUN 28 1966
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Rains & Williamson Oil Co.
Address 1425 Wichita Plaza Bldg., Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Wilson Rains, Partner (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Wilson Rains
Wilson Rains
1425 Wichita Plaza Bldg., Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN to before me this 27th day of June, 19 66

My commission expires 3-3-70

Mary J. Brown
Mary J. Brown Notary Public.

ROTARY DRILLING LOG

Operator: Rains & Williamson Oil Co.
#1 Bowers
C NW NW Sec. 23-27S-20W
Kiowa County, Kansas

Contractor: Rains & Williamson Oil Co.
Commenced: 6-10-66
Completed: 6-22-66
Remarks: Set 556.82° of 8-5/8" surface
pipe with 280 sacks of GL3.

Formations:

| | |
|----------------------------|-------|
| Sand & Shale | 560° |
| Shale & Shells | 670° |
| Shale & Red Bed | 1482° |
| Anhydrite | 1504° |
| Shale & Lime Streaks | 2300° |
| Lime & Shale | 2705° |
| Lime | 2840° |
| Lime & Shale | 4235° |
| Lime | 4800° |
| Lime - Shale | 4835° |
| Lime | 4877° |
| Chert & Lime | 4890° |
| Rotary Total Depth (D & A) | 4890° |

RECEIVED
STATE CORPORATION COMMISSION

JUN 28 1966

CONSERVATION DIVISION
Wichita, Kansas

We certify the above log is true and
correct to the best of our knowledge
and belief.

RAINS & WILLIAMSON OIL CO.

Wilson Rains
Wilson Rains, Partner

Subscribed and sworn to before me, a Notary Public in and for the State of
Kansas, County of Sedgwick, this 27th day of June, 1966.

My Commission Expires: 3-3-70

Mary J. Brown
Mary J. Brown Notary Public