


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202

Kiowa County. Sec. 22 Twp. 27S Rge. 20W E/W  
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines  
1980' FSL & 660' FEL  
Lease Owner Texas Oil & Gas Corp.  
Lease Name Brensing "A" Well No. 1  
Office Address 200 W. Douglas-Suite 300, Wichita, KS  
Character of Well (Completed as Oil, Gas or Dry Hole) 67202



Locate well correctly on above  
Section Plot

Dry Hole  
Date Well completed May 24, 1980  
Application for plugging filed Verbal Application 1980  
Application for plugging approved Verbal Approval 1980  
Plugging commenced May 24, 1980  
Plugging completed May 24, 1980  
Reason for abandonment of well or producing formation \_\_\_\_\_

If a producing well is abandoned, date of last production \_\_\_\_\_ 1980

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well William T. Owen  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4,950'  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	562'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with heavy rotary mud from 4,950 ft. (rotary total depth) to 450 ft. Set plug at 450 ft. and cemented with 40 sacks cement. Filled hole with heavy rotary mud from 450 ft. to 40 ft. Set solid plug at 40 ft. and cemented to cellar with 10 sacks cement, 5 sacks cement in rat hole and 2 sacks cement in water well.

Plugging operations accomplished utilizing Dowell Oil Well cementing pump truck through 4 1/2 inch drill pipe.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Dowell Div., Dow Chemical Co.  
Hwy. 281 & Santa Fe, Pratt, Kansas


STATE OF Kansas COUNTY OF Sedgwick  
Dean Britting, Agent (Employee of owner XXXXXXXXXXXXXXXXXXXX)

of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dean Britting 6-16-80  
251 N. Water - Suite 10, Wichita, KS 67202  
(Address)

SUBSCRIBED AND SWORN TO before me this 6th day of June, 1980

My commission expires July 25, 1982  
Elsie Willison  
Elsie Willison - Notary Public.



KANSAS DRILLERS LOG

COMPANY Texas Oil & Gas Corp.

SEC. 22 T. 27S R. 20W  
LOC. 1980' FSL & 660' FEL

FARM Brensing "A" NO. 1

COUNTY Kiowa

ROTARY TOTAL DEPTH 4,950'  
COMM. May 15, 1980 COMP. May 24, 1980  
CONTRACTOR H-30, Inc. (Rig #5)  
ISSUED June 6, 1980

CASING

10 3/4"  
8 5/8" Set at 562' cemented w/400 sxs cement  
5 1/2"  
4 1/2"

ELEVATION 2,304' K.B.

FIGURED INDICATE BOTTOM OF FORMATIONS

Sand	560'
Shale and Red Bed	585'
Red Bed and Shale	1,668'
Shale and Lime	2,468'
Lime and Shale	2,721'
Shale and Lime	2,970'
Lime and Shale	3,366'
Shale and Lime	3,609'
Lime and Shale	4,089'
Shale and Lime	4,664'
Lime and Shale	4,715'
Shale and Lime	4,897'
Lime and Shale	4,950'
Rotary Total Depth	4,950'

I hereby certify the above and foregoing to be a true and correct log of the above described well as shown by the drilling reports.

H-30, INC.

*Dean Britting*  
Dean Britting

State of Kansas )  
                          ) SS:  
County of Sedgwick )

Subscribed and Sworn to before me a Notary Public in and for said county and state this 6th day of June, 1980.

*Elsie Willison*  
Elsie Willison - Notary Public



My Commission Expires:  
July 25, 1982

