

API NUMBER 15-097-30098-0001

LEASE NAME Brensing "A" #1

WELL NUMBER _____

SPOT LOCATION SE NW

SEC. 33 TWP. 27s RGE. 20w (W) or (W)

COUNTY Kiowa

Date Well Completed _____

Plugging Commenced 7/11/84

Plugging Completed 7/18/84

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

LEASE OPERATOR Southwind Petroleum Corp.

ADDRESS 1825 W. 13th ST. Wichita, Ks. 67203

PHONE # (316) 267-0305 OPERATORS LICENSE NO. 6743

Character of Well _____
(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Did you notify the KCC/KDHE Joint District Office prior to plugging this well? Yes

Which KCC/KDHE Joint Office did you notify? Dodge City

Is ACO-1 filed? _____ If not, is well log attached? _____

Producing formation _____ Depth to top _____ bottom T.D. 4970'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put in	Pulled out
				8 5/8	635'	none
				4 1/2"	4966'	2513'

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used state, the character of same and depth placed, from _____ feet to _____ feet each set.

Pumped bottom with 35 sacks cement to 4600'. Shot pipe at 4002', 3524', 3219', 3001', 2817', 2722', & 2513'. Pulled 68 joints of pipe. Started plugging well with 3 hulls, 15 gel, 50 cement, 10 gel, & 1 hull. Started to circulate out of ground. Drilled out to 635' & ran 150 sacks 50/50 poz 2% gel 3% c.c.

Plugging complete
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Kelso Casing Pulling License No. 6050

Address Box 347, Chase, Ks. 67524


STATE OF Kansas COUNTY OF Rice, ss.

R. Darrell Kelso (employee of operator) or (operator) of above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.

(Signature) R. Darrell Kelso

(Address) Box 347, Chase, Ks. 67524

SUBSCRIBED AND SWORN TO before me this 31st day of July, 1984



Irene Hoover
Notary Public

My Commission Expires: AUG 02 1984

8-2-84

RECEIVED
STATE CORPORATION COMMISSION