

Form CP-3  
Rev. 6-26-62

KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

**RECEIVED**  
STATE CORPORATION COMMISSION

JUN 15 1964

CONSERVATION DIVISION  
Wichita, Kansas

Operator's Full Name Skelly Oil Company

Complete Address: P. O. Box 649, McCook, Nebraska

Lease Name Wendel Leisman Well No. # 2

Location C SW SW SW Sec. 20 Twp. 27 Rge. 10 (E) (W) W

County Kingman Total Depth 3408

Abandoned Oil Well X Gas Well      Input Well      SWD Well      D & A     

Other well as hereafter indicated:     

Plugging Contractor: Ace Pipe Pulling Co.

Address: Box 304, Great Bend, Kansas License No. 2

Operation Completed: Hour 3:00PM Day 11th Month June Year 1964

The Above well was plugged as follows:

247' of 12½" surface pipe, cemented with 170 sacks. 3376' of 5½" long  
string, cemented with 425 sacks. Plug back to 3012'. Bottom of hole  
was sanded to 2950', and cemented with 4 sacks. Hole was filled with  
mud to 265', with 10' of rock bridge, and cemented with 35 sacks, brin-  
ging the top of the cement to 203' in the surface pipe. Hole was filled  
with mud to 35', with 10' of rock bridge, and cemented with 15 sacks to  
the base of the cellar.

268' of 5½" long string was recovered from the hole.

I hereby certify that the above well was plugged as herein stated.

**INVOICED**

Signed: Archie Elving  
Well Plugging Supervisor

DATE 6/15/64

INV. NO. 9310-W