

10
KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

JUN 19 1964

CONSERVATION DIVISION
Wichita, Kansas

Operator's Full Name Skelly Oil Company

Complete Address: P. O. Box 649, McCook, Nebraska

Lease Name Wendel Leisman Well No. # 5

Location App. NW SW SW Sec. 20 Twp. 27 Rge. 10 (E) (W) W

County Kingman Total Depth 3489

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Ace Pipe Pulling Co.

Address: Box 304, Great Bend, Kansas License No. 2

Operation Completed: Hour 6:30PM Day 16th Month June Year 1964

The Above well was plugged as follows:

321' of 12 1/2" surface pipe, cemented with 300 sacks. 3400' of 7" long
string, cemented with 500 sacks. Plug back to 3486'. Bottom of the hole
was sanded to 3380', and cemented with 5 sacks. Hole was filled with mud
to 300', with 10' of rock bridge, and cemented with 35 sacks. Hole was
filled with mud to 40', with 10' of rock bridge, and cemented with 15
sacks to base of the cellar.

1700' of 7" long string was recovered from the hole.

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 6/19/64

INV. NO. 9334-11

Signed: Archie Elving
Well Plugging Supervisor