

15-095-19101-0001

Form CP-3
Rev. 6-26-62KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
KANSAS CORPORATION COMMISSION

JAN 23 1967

CONSERVATION DIVISION
Wichita, KansasJ. P. Roberts
Assitant Director
500 Insurance Building
212 North Market
Wichita 2, KansasWell Plugging Authority,
issued December 5, 1966

Operator's Full Name Skelly Oil Company

Complete Address: P. O. Box 649, McCook, Nebraska

Lease Name Miles "A" Well No. # 10

Location SE NE NW Sec. 29 Twp. 27 Rge. 10 (E) (W) W

County Kingman Total Depth 4430'

Abandoned Oil Well X Gas Well Input Well SWD Well D & A

Other well as hereafter indicated:

Plugging Contractor: Comstock Pipe Pulling, Inc.

Address: Stafford, Kansas License No. 490

Operation Completed: Hour 12:00PM Day 21st Month Jan. Year 1967

The Above well was plugged as follows:

308' of 12½" surface pipe, cemented with 300 sacks. 3426' of 7" long string,
cemented with 500 sacks, bringing the cement to 46' of the top. 2731' of 4½"
liner, cemented with 100 sacks. Tubing was ate up, and sanded in, and had
parted at 986'. 4½" liner was sanded in the 7" to the top. No recovery of
any pipe. Bridge plug was pushed in 4½"liner to the top of the tubing at
986', sand to 970'. Hole was filled with 4 yards of ready-mix cement from
970' to the base of the cellar. A steelcap was welded over all the pipe.

I hereby certify that the above well was plugged as herein stated.

INVOICED

Signed: Achie Elving
Well Plugging SupervisorDATE 1/23/67INV. NO. 4649-W